SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT		ROADWAY 1000
20200100	EARTH EXCAVATION	CU YD	120	120
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	20	20
35800200	AGGREGATE BASE REPAIR	TON	160	160
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	15	15
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	42	42
40600300	AGGREGATE (PRIME COAT)	TON	206	206
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	6	6
40600535	LEVELING BINDER (HAND METHOD), N70	TON	25	25
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	650	650
40600990	TEMPORARY RAMP	SQ YD	820	820
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	460	460
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2	2
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	5,200	5,200
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	20	20
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	500	500
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	51,200	51,200
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	40	40
44000600	SIDEWALK REMOVAL	SQ FT	500	500
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	400	400
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	2,000	2,000
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1,300	1,300
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	280	280
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	150	150
55039700	STORM SEWERS TO BE CLEANED	FOOT	2,800	2,800
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	4	4
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	5	5

* DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT		ROADWAY 1000
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	105	105
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	3	3
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	3	3
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11,000	11,000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2,100	2,100
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	62,100	62,100
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	13,200	13,200
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,400	2,400
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	2,400	2,400
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	12,200	12,200
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	700	700
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20,700	20,700
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4,400	4,400
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	800	800
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	800	800
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	780	780
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	742	742
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,900	1,900
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2,950	2,950
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	195	195

Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel: 773.775.4009 Fax 773.775.4014