

SUMMARY OF QUANTITIES				URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000	
20201006	GRADING AND SHAPING SHOULDERS	UNIT	160	160	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	20	20	
40600300	AGGREGATE (PRIME COAT)	TON	96	96	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	4	4	
40600535	LEVELING BINDER (HAND METHOD), N70	TON	2	2	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	265	265	
40600990	TEMPORARY RAMP	SQ YD	380	380	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	90	90	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,100	2,100	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	23,600	23,600	
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	550	550	
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	10	10	
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	90	90	
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	100	100	
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	100	100	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	680	680	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	

* DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES				URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4,850	4,850	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	330	330	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	31,100	31,100	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,500	1,500	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,300	1,300	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	400	400	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,500	4,500	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110	110	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	26,100	26,100	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	500	500	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	420	420	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	130	130	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	220	220	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	200	200	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	110	110	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,300	1,300	
* X0326478	TREE PRUNING, SPECIAL	UNIT	100	100	

FILE NAME = m:\pco\3388\3388-16\design\proposedplan\3388-16-03-Quantities.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = alou	DESIGNED - RJR	REVISED -
	DRAWN - RJR	REVISED -
PLOT SCALE = 1:2000' / IN.	CHECKED - WBL	REVISED -
PLOT DATE = 4/16/2009	DATE - 4/22/2009	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

FLAVIN ROAD 107TH STREET TO 95TH STREET SUMMARY OF QUANTITIES	
SCALE:	SHEET NO. 3 OF 16 SHEETS STA. TO STA.

F.A.I.L. RTE. 2697	SECTION 3117 RS-3	COUNTY COOK	TOTAL SHEETS 16	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60G84	