

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT		TOTAL QUANTITIES	WEST 1000	EAST 1000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	11	4	7														
40600300	AGGREGATE (PRIME COAT)	TON	46	15	31														
40600895	CONSTRUCTING TEST STRIP	EACH	4	2	2														
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	50	25	25														
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	2880	950	1930														
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	960	317	643														
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	207	69	138														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	2	4														
67100100	MOBILIZATION	L SUM	1	0.3	0.7														
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.3	0.7														
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.3	0.7														
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	32994	10998	21996														
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10539	3513	7026														
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	11302	3970	7332														
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10539	3513	7026														
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	170	65	105														
X0321374	GRADING AND SHAPING SHOULDERS	FOOT	10080	3360	6720														
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	104	52	52														
XX003535	AGGREGATE BASE COURSE, TYPE B, 2"	SO YD	11105	3665	7440														
XX006047	PULVERIZATION	SO YD	11105	3665	7440														
* SPECIALTY ITEMS																			

FILE NAME =	USER NAME = mosses	DESIGNED -	REVISED -
colpr_work\N\DOT\MOSSSE\0136450\055309-011\plandgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.U. RTE. 0388	SECTION 99-2AC-3RS-3	COUNTY WILL	TOTAL SHEETS 12	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60G97	