

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I-000						CODE NO	ITEM		UNIT				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	27	27													
31101300	SUB-BASE GRANULAR MATERIAL, TYPE B 5"	SO YD	4357	4357													
35800100	PREPARATION OF BASE	SO YD	4357	4357													
35800200	AGGREGATE BASE REPAIR	TON	1211	1211													
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	2													
40600300	AGGREGATE (PRIME COAT)	TON	9	9													
40600895	CONSTRUCTING TEST STRIP	EACH	3	3													
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	732	732													
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	366	366													
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	211	211													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1													
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3709	3709													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6499	6499													
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	412	412													
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6499	6499													
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	20	20													
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4													

* SPECIALITY ITEMS