

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000						CODE NO	ITEM		UNIT				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	392	392													
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	18	18													
40600300	AGGREGATE (PRIME COAT)	TON	90	90													
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	14	14													
40600895	CONSTRUCTING TEST STRIP	EACH	1	1													
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	69	69													
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	75	75													
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3767	3767													
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	44835	44835													
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	672	672													
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	10	10													
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	170	170													
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	70	70													
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	350	350													
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1305	1305													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1													
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1													
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10668	10668													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	53500	53500													
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	88	88													
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3556	3556													
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	53500	53500													
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	88	88													
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	375	375													
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	375	375													
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4													
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1766	1766													
										* SPECIALTY ITEMS							