

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE								
CODE NO	ITEM	UNIT	TOTAL QUANTITIES		1000						CODE NO	ITEM	UNIT	TOTAL QUANTITIES		1000					
			URBAN 100% STATE											URBAN 100% STATE							
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15		15						X032256	TEMPORARY INFORMATION SIGNING	SO FT	106.3		106.3					
40600300	AGGREGATE (PRIME COAT)	TON	76		76						X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50	TON	1485		1485					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	11		11						XX002258	STRUCTURES TO BE ADJUSTED	EACH	1		1					
40600895	CONSTRUCTING TEST STRIP	EACH	1		1						20018200	DRAINAGE STRUCTURE RECONSTRUCTION (SPECIAL)	EACH	1		1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	93		93						20018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	7		7					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	45		45																
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3168		3168																
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	37717		37717																
44002215	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 3/4"	SO YD	1974		1974																
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SO YD	1000		1000																
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SO YD	200		200																
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SO YD	720		720																
55039700	STORM SEWERS TO BE CLEANED	FOOT	350		350																
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	200		200																
67000400 67100100	ENGINEER'S FIELD OFFICE, TYPE A MOBILIZATION	CAL MO L SUM	0 1		0 1																
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		1																
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1																
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2407		2407																
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	100		100																
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	25378		25378																
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1098		1098																
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1378		1378																
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	100		100																
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	25378		25378																
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1098		1098																
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1378		1378																
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	340		340																
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	173		173																

* Specialty Items