

SUMMARY OF QUANTITIES				URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000	
20200100	EARTH EXCAVATION	CU YD	70	70	
35800200	AGGREGATE BASE REPAIR	TON	100	100	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	50	50	
40600300	AGGREGATE (PRIME COAT)	TON	250	250	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	8	8	
40600535	LEVELING BINDER (HAND METHOD), N70	TON	10	10	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	796	796	
40600990	TEMPORARY RAMP	SQ YD	1,270	1,270	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	6,200	6,200	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	20	20	
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	1,000	1,000	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	60,500	60,500	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	20	20	
44000600	SIDEWALK REMOVAL	SQ FT	1,000	1,000	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	800	800	
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	1,150	1,150	
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	250	250	
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	550	550	
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	220	220	
55039700	STORM SEWERS TO BE CLEANED	FOOT	2,700	2,700	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	3	3	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10	10	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	175	175	

* DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES				URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000	
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	15	15	
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	15	15	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10,710	10,710	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	600	600	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	54,200	54,200	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	22,800	22,800	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,200	1,200	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	200	200	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	6,000	6,000	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	14,400	14,400	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	200	200	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	19,000	19,000	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	7,600	7,600	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	400	400	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	65	65	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	2,000	2,000	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51	51	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3,300	3,300	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	240	240	

FILE NAME = N:\PROJ\3368\3368.17\Design\ProposedPlan\3368.17-09-Quantities.dgn



Ciorka Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = alau	DESIGNED - MT	REVISED -
	DRAWN - MT	REVISED -
PLOT SCALE = 1.0000' / IN.	CHECKED - WBL	REVISED -
PLOT DATE = 4/21/2009	DATE - 4/22/09	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SHERIDAN ROAD
ARTHUR AVENUE TO NORTH OF JUNEWAY TERRACE
SUMMARY OF QUANTITIES**

F.A.U. RATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2865	2829 RS-4	COOK	18	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60H10	

SCALE: SHEET NO. 3 OF 18 SHEETS STA. TO STA.