

URBAN
100% STATE I000

| CODE NO. | SUMMARY OF QUANTITIES ITEM DESCRIPTION | UNIT | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE URBAN |
|---------------------|--|------------------|---------------------|---------------------------------|
| 40600100 | BITUMINOUS MATERIALS (PRIME COAT) | GALLON | 7,037 | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 141 | |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 14 | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 160 | |
| 40601005 | HOT-MIX ASPHALT REPLACEMENT OVER PATCHES | TON | 676 | |
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 | TON | 5,911 | |
| 44000159 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2" | SQ YD | 70,365 | |
| 44001700 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 100 | |
| 44201785 | CLASS D PATCHES, TYPE I, 12 INCH | SQ YD | 70 | |
| 44201789 | CLASS D PATCHES, TYPE II, 12 INCH | SQ YD | 281 | |
| 44201794 | CLASS D PATCHES, TYPE III, 12 INCH | SQ YD | 985 | |
| 44201796 | CLASS D PATCHES, TYPE IV, 12 INCH | SQ YD | 2,111 | |
| 44002214 | HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2" | SQ YD | 3,447 | |
| 48102100 | AGGREGATE WEDGE SHOULDER, TYPE B | TON | 2,374 | |
| 60300105 | FRAMES AND GRATES TO BE ADJUSTED | EACH | 2 | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 8 | |
| 67100100 | MOBILIZATION | L SUM | 1 | |
| 70100450 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201 | L SUM | 1 | |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 | |
| 70100600 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701336 | L SUM | 1 | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 29,633 | |
| * 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 59,266 | |
| * 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 50 | |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 59,266 | |
| * 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 50 | |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 340 | |
| * 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 340 | |
| X0322256 | TEMPORARY INFORMATION SIGNING | SQ FT | 103 | |
| X4067107 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 | TON | 3,694 | |

* SPECIALTY ITEM