

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 1000					CODE NO	ITEM	UNIT		URBAN 1000				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	55	55					70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	74	74				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	20	20					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	20575	20575				
40600300	AGGREGATE (PRIME COAT)	TON	90	90					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	171	171				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	7	7					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	133	133				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	542	542				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	84	84				* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	74	74					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	176	176				* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20575	20575					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2201	2201				* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	171	171					
42001300	PROTECTIVE COAT	SQ YD	267	267				* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	133	133					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	22453	22453				* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	369	369					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	600	600				78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	369	369					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1045	1045				* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	132	132					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	673	673				X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	69	69				X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	745	745					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	274	274				Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	12	12					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	433	433													
55039700	STORM SEWERS TO BE CLEANED	FOOT	300	300													
60250200	CATCH BASINS TO BE ADJUSTED	EACH	8	8													
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	6	6													
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2													
60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	8	8													
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	4	4													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1													
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4293	4293													

\* Specialty Items

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL 19 (IRVING PARK RD.)  
DES PLAINES RIVER RD. TO IL-171 (CUMBERLAND AVE.)  
SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
345	2003-091 RS	COOK	19	3
CONTRACT NO. 62666				

SCALE: SHEET NO. OF SHEETS STA. TO STA.

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT