



LEGEND

- ① PROPOSED THERMOPLASTIC PAVEMENT MARKING, 4" DOUBLE SOLID YELLOW LINE AT 11" C-C (TYP.)
- ② PROPOSED THERMOPLASTIC PAVEMENT MARKING, 6" WHITE CROSSWALK LINES (SOLID) AT 6' APART (TYP.)
- ③ PROPOSED THERMOPLASTIC PAVEMENT MARKING, 24" WHITE LINE, STOP BAR (TYP.)
- ④ PROPOSED THERMOPLASTIC PAVEMENT MARKING, 12" WHITE (3' C-C)
- ⑤ PROPOSED THERMOPLASTIC PAVEMENT MARKING, 4" WHITE EDGE LINE, (TYP.)
- ⑥ PROPOSED THERMOPLASTIC PAVEMENT MARKING, 4" LINE SKIP DASH (10' DASH, 30' SKIP) YELLOW ☉
- ⑦ PROPOSED THERMOPLASTIC PAVEMENT MARKING, 4" DOTTED LINE (2' DASH, 6' SKIP) WHITE
- ⑧ PROPOSED THERMOPLASTIC PAVEMENT MARKING, 8" LINE SOLID WHITE
- ⑨ PROPOSED THERMOPLASTIC PAVEMENT MARKING, 12" LINE SOLID WHITE DIAGONAL 12" C-C @ 45°
- ⑩ PROPOSED THERMOPLASTIC PAVEMENT MARKING, 6" LINE SOLID WHITE LEFT TURN LANE
- ⑪ PROPOSED THERMOPLASTIC PAVEMENT MARKING, WHITE LETTERS & SYMBOLS
- ⑫ PROPOSED THERMOPLASTIC PAVEMENT MARKING, 4" SOLID YELLOW LINES (5 1/2" C-C)

FILE NAME =	USER NAME = smithkl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	RIDGE RD. (WILMETTE AVE. TO WINNETKA RD.) ROADWAY AND PAVEMENT MARKING PLAN	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\pwork\pwidot\SMITHKL\0125091\Design.dgn		DRAWN -	REVISED -			3520	2005-01ORS	COOK	23	7	
PLOT SCALE = 50.0001' / IN.		CHECKED -	REVISED -			CONTRACT NO. 62927					
PLOT DATE = 3/26/2009		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					