

GENERAL NOTES

THE THICKNESS OF HMA SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA IS PLACED.

THE ENGINEER WILL BE THE SOLE JUDGE CONCERNING CURING TIME FOR THE VARIOUS HMA LIFTS.

ENTRANCES AND SIDEROADS WILL NOT BE MILLED AND RESURFACED AS PART OF THIS IMPROVEMENT WITH THE EXCEPTION OF US 52. US 52 WILL BE MILLED AND RESURFACED BACK TO THE CONSTRUCTION JOINT APPROXIMATELY 30 FEET FROM THE EDGE OF IL 251.

FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES:

GRANULAR MATERIALS	2.05	TONS / CU YD
BITUMINOUS MATERIALS (PRIME COAT)	0.08	GAL / SQ YD
FOR ADDITIONAL HMA LIFTS "FOG COAT"	0.05	GAL / SQ YD
AGGREGATE PRIME COAT	0.002	TONS / SQ YD
HMA RESURFACING	112	LBS / SQ YD / IN
SHORT TERM PAVEMENT MARKING	10	FT / 100 FT OF APPLICATION
MIX FOR CRACKS, JTS & FLGWYS	0.0003	TONS / SQ YD
LEVEL BINDER (HAND METHOD)	0.0005	TONS / SQ YD

THE CONTRACTOR SHALL CONTACT JULIE AT LEAST 48 HOURS PRIOR TO EXCAVATION TO DETERMINE WHICH UTILITIES ARE IN THE AREA.

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE

PREPARED BY: *R. J. Howell*
DISTRICT STUDIES & PLANS ENGINEER

DATE: 3/25/09

EXAMINED BY: *Herb Jung*
DISTRICT CONSTRUCTION ENGINEER

Wayne Anderson
DISTRICT MATERIALS ENGINEER

Bruce A. Heuchman
DISTRICT OPERATIONS ENGINEER

FILE NAME =	USER NAME = lindemanns	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwork\lindemanns\d0122862\366969-shr-cover.dgn	DRAWN -	REVISED -	250			(71,72)RS-6	LASALLE	12	2		
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 66969								
PLOT DATE = Mar 25, 2009 - 08:58:02 AM	DATE -	REVISED -	ILLINOIS FED. AID PROJECT								
						SCALE: _____	SHEET NO. ____ OF ____ SHEETS	STA. _____ TO STA. _____			