

SUMMARY OF QUANTITIES			100% STATE
CODE NO.	CONSTRUCTION CODE TYPE:		1000
	ITEM	UNIT	TOTAL
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	31285
40600300	AGGREGATE (PRIME COAT)	TON	596
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	45
40600535	LEVELING BINDER (HAND METHOD), N70	TON	74
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	6257
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600990	TEMPORARY RAMP	SQ YD	59
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D",N70	TON	12514
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	148979
48101200	AGGREGATE SHOULDERS, TYPE B	TON	10883
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	12
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	13168
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	78
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	132240
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	14426
70300640	TEMPORARY PAINT PAVEMENT MARKING LINE 8"	FOOT	550
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	670
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	35
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2192
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	78
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8756
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	550
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	670
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	35
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	123484
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	14426
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	799
78200300	PRISMATIC CURB REFLECTOR	EACH	8
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	799
X0326471	HOT-MIX ASPHALT FOR PATCHING	TON	1830
X0326472	HOT-MIX ASPHALT REMOVAL	SQ YD	14525

* SPECIALTY ITEMS

FILE NAME =	USER NAME = Lindemann	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cs:\pav\work\projects\lindemann\14002082	366969-ah-300.DGN	DRAWN -	REVISED -		250	(71,72)RS-6	LASALLE	12	3		
PLDT SCALE = 58.0000' / IN.	CHECKED -	REVISED -			SCALE: _____ SHEET NO. ____ OF ____ SHEETS STA. _____ TO STA. _____		CONTRACT NO. 66969				
PLDT DATE = Mar 25, 2009 - 08:55:43 AM	DATE -	REVISED -					ILLINOIS FED. AID PROJECT				