

PERMANENT AND TEMPORARY PAVEMENT MARKINGS						
Location	Urethane			Preformed Plastic Type B	Raised Reflective Pavement Markers	Raised Reflective Pavement Markers Removal
	4"	8"	12"	6"		
	Foot	Foot	Foot	Foot	Each	Each
<b>Northbound</b>						
418+52 to 428+28	1951			488	26	26
56+28 to 186+92	26129			4110	203	203
186+91 to 249+00	12418			1553	78	78
248+99 to 449+28	40059			5008	251	251
56+08 to 63+00	1385			174	9	9
Maxwell Road Ramp		436	6		6	6
Airport Road - Ramp C		732				
Airport Road - Ramp A		463	20		10	10
US 24 - Ramp A		610				
US 24 - Ramp F		490	18		7	7
<b>Southbound</b>						
519+29 to 528+21	1784			448	24	24
55+39 to 186+92	26307			4132	204	204
186+91 to 249+00	12418			1553	78	78
248+99 to 449+28	40059			5008	251	251
56+08 to 63+00	1385			174	9	9
Maxwell Road - Ramp A		541	18		14	14
Maxwell Road - Ramp E		754				
Airport Road - Ramp D		487	21		7	7
US 24 - Ramp D		463	20		7	7
US 24 - Ramp E		745				
US 24 - Ramp C		171				
<b>TOTAL</b>	<b>163892</b>	<b>5892</b>	<b>103</b>	<b>22648</b>	<b>1184</b>	<b>1184</b>

SHORT TERM PAVEMENT MARKING						WORK ZONE PAVEMENT MARKING REMOVAL
Location	Length	Dash	Shoulder	x3 Apps	Sq Ft	
					Foot	Foot
<b>Northbound</b>						
418+52 to 428+28	1951.36	195	78	819		273
56+28 to 186+92	13907	1391	556	5841		1947
186+91 to 249+00	6208.84	621	248	2607		869
248+99 to 449+28	20029.3	2003	801	8412		2804
56+08 to 63+00	692.27	69	28	291		97
<b>Southbound</b>						
519+29 to 528+21	1784.02	178	71	747		249
55+39 to 186+92	13996	1400	560	5880		1960
186+91 to 249+00	6208.84	621	248	2607		869
248+99 to 449+28	20029.3	2003	801	8412		2804
56+08 to 63+00	692.27	69	28	291		97
<b>Total</b>				<b>17679</b>		<b>5893</b>

Centerline = 4' per 40'  
Shoulder = 4' diagonal every 100'