

SUMMARY OF QUANTITIES

CONSTR. CODE
PEORIA COUNTY
100% STATE
ROADWAY
1000
RURAL

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | ROADWAY 1000 RURAL |
|----------|---|-------|----------------|--------------------------|
| 20200600 | EXCAVATING ^{AND} GRADING EXISTING SHOULDER | UNIT | 465 | 465 |
| 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL | CU YD | 3406 | 3406 |
| 20700220 | POROUS GRANULAR EMBANKMENT | CU YD | 579 | 579 |
| 20800150 | TRENCH BACKFILL | CU YD | 206 | 206 |
| 21001000 | GEOTECHNICAL FABRIC FOR GROUND STABILIZATION | SQ YD | 3406 | 3406 |
| 28000500 | INLET AND PIPE PROTECTION | EACH | 1 | 1 |
| 28200200 | FILTER FABRIC | SQ YD | 375 | 375 |
| 31100100 | SUB-BASE GRANULAR MATERIAL, TYPE A | TON | 2323.7 | 2323.7 |
| 40600215 | POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT) | TON | 146.8 | 146.8 |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 848.4 | 848.4 |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 1 | 1 |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 6180 | 6180 |
| 40600990 | TEMPORARY RAMP | SQ YD | 489 | 489 |
| 40603335 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 | TON | 21671 | 21671 |
| 40800050 | INCIDENTAL HOT-MIX ASPHALT SURFACING | TON | 343 | 343 |
| 42000500 | PORTLAND CEMENT CONCRETE PAVEMENT 10" | SQ YD | 2291.7 | 2291.7 |
| 42001200 | PAVEMENT FABRIC | SQ YD | 2291.7 | 2291.7 |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 2194.1 | 2194.1 |
| 44000152 | HOT-MIX ASPHALT SURFACE REMOVAL, 3/4" | SQ YD | 73200 | 73200 |
| 44000154 | HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4" | SQ YD | 833 | 833 |
| 44000155 | HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" | SQ YD | 171805 | 171805 |
| 44000157 | HOT-MIX ASPHALT SURFACE REMOVAL, 2" | SQ YD | 13608 | 13608 |

* Denotes Specialty Item.

SUMMARY OF QUANTITIES

CONSTR. CODE
PEORIA COUNTY
100% STATE
ROADWAY
1000
RURAL

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | ROADWAY 1000 RURAL |
|----------|--|-------|----------------|--------------------------|
| 44000400 | GUTTER REMOVAL | FOOT | 669 | 669 |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 543 | 543 |
| 44000920 | BITUMINOUS CONCRETE SHOULDER REMOVAL | SQ YD | 445.4 | 445.4 |
| 44200132 | PAVEMENT ^{PATCHING} TYPE II, 11 INCH | SQ YD | 976 | 976 |
| 44200136 | PAVEMENT ^{PATCHING} TYPE III, 11 INCH | SQ YD | 224 | 224 |
| 44200138 | PAVEMENT ^{PATCHING} TYPE IV, 11 INCH | SQ YD | 187 | 187 |
| 44201811 | CLASS D PATCHES, TYPE I, 14 INCH | SQ YD | 20 | 20 |
| 44201815 | CLASS D PATCHES, TYPE II, 14 INCH | SQ YD | 748 | 748 |
| 44201819 | CLASS D PATCHES, TYPE III, 14 INCH | SQ YD | 41 | 41 |
| 44201827 | CLASS D PATCHES, TYPE II, 15 INCH | SQ YD | 859 | 859 |
| 44201831 | CLASS D PATCHES, TYPE III, 15 INCH | SQ YD | 85 | 85 |
| 44201833 | CLASS D PATCHES, TYPE IV, 15 INCH | SQ YD | 120 | 120 |
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 5519 | 5519 |
| 48203029 | HOT-MIX ASPHALT SHOULDERS, 8" | SQ YD | 20647 | 20647 |
| 48203100 | HOT-MIX ASPHALT SHOULDERS | TON | 204 | 204 |
| 48300500 | PORTLAND CEMENT CONCRETE SHOULDERS 10" | SQ YD | 398.2 | 398.2 |
| 550A0070 | STORM SEWERS, CLASS A, TYPE 1 15" | FOOT | 116 | 116 |
| 550A0090 | STORM SEWERS, CLASS A, TYPE 1 18" | FOOT | 98 | 98 |
| 550A0140 | STORM SEWERS, CLASS A, TYPE 1 30" | FOOT | 47 | 47 |
| 55100500 | STORM SEWER REMOVAL 12" | FOOT | 34 | 34 |
| 55100700 | STORM SEWER REMOVAL 15" | FOOT | 119 | 119 |
| 55100900 | STORM SEWER REMOVAL 18" | FOOT | 33 | 33 |

* Denotes Specialty Item.