

ROUTE		SECTION	COUNTY	SHEET	
F.A.	VAR	*	PEORIA	TOTAL	NO.
MKD.	US 150			100	10

***(108X,130,102)RS-3;129RS-4,101RS-2**

Summary of Quantities			ROUTE	SECTION	COUNTY	SHEET	
Code Order			FAS	100	PEORIA	TOTAL	NO.
			US	150			

CONSTRUCTION TYPE CODE			
ROADWAY			
1000			

CODE No.	ITEM	UNIT	Tot.QTY
----------	------	------	---------

40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	18	18
40600300	AGGREGATE (PRIME COAT)	TON	133	133
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	845	845
40600990	TEMPORARY RAMP	SQ YD	194	194
40603335	HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	3741	3741
44000155	HOT - MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	44374	44374
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	859	859
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SQ YD	85	85
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SQ YD	120	120
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2282	2282
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1

(X)Specialty Item

06-Apr-09

Page 1 of 3

FOR INFORMATION ONLY

SUMMARY OF QUANTITIES
US 150