

ENVIRONMENTAL REVIEWS

Prior to the use of any proposed borrow areas, use areas (temporary access roads, detours, run-arounds, etc.) and/or waste areas, the Contractor shall file the required environmental resource request surveys according to Section 107.22 of the Standard Specifications. These surveys are required in order for the Department to conduct cultural and biological resource surveys for the proposed site.

Prior to any waste materials being removed from the construction site the required environmental resource surveys will need to be obtained and filed by the Contractor. Excess waste products removed from the construction site shall be disposed of as required in Section 202.03 of the Standard Specifications.

Any protruding metal bars shall be removed prior to the disposal of broken concrete at approved disposal sites.

The required environmental resource documentation shall include the following:

- * BDE Form 2289 (Environmental Survey Request)
- * A location map showing the size limits and location of the use area
- * Signed property owner agreement form-D4 PI0100
- * Color photographs depicting the use area
- * Borrow Area Entry Agreement form-D4 PI0101

Please note that a minimum of two weeks shall be allowed for the District to obtain the required environmental clearances.

Job Specific Note

The limits and quantities of removal and replacement of unsuitable material shown is based on the boring data. After removal of the existing pavement the District Geotechnical Engineer is to be contacted to establish the final removal limits for Unsuitable Material.

Status of Utilities

Sta. 655 + 55	Crossing	Ameren	2" HP Gas	Caution
Sta. 658 + 60	Aerial in Viaduct	Verizon	Adjust to clear phase II traffic	
Sta. 661 + 90	Crossing	Buckeye	Oil Line 3' below pavement	Caution

A minimum of 14 feet vertical clearance shall be established at the centerline from the proposed pavement to the low steel of the viaduct.

The Engineer shall coordinate with the Village of Laura and the adjacent property owners regarding impacts to entrance and street access during construction.

COMMITMENTS

No Commitments have been made for this project.

FOR INFORMATION ONLY

FILE NAME = 0468890-Design.dgn	USER NAME = everscl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES & COMMITMENTS	F.A.P. RTE. 22	SECTION .	COUNTY PEORIA	TOTAL SHEETS 100	SHEET NO. 30	
	PLOT SCALE = 80.0000' / IN.	CHECKED -	REVISED -			* (108X,130,102)RS-3;129RS-4,101RS-2		CONTRACT NO. 68890		[ILLINOIS] FED. AID PROJECT	
	PLOT DATE = 4/6/2009	DATE -	REVISED -			SCALE: _____	SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____			