

SUMMARY OF QUANTITIES for Information Only

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	PEORIA COUNTY 1000
20200600	EXCAVATING & GRADING EXISTING SHOULDER	UNIT	465	465
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	49	49
40600300	AGGREGATE (PRIME COAT)	TON	280	280
40600895	CONSTRUCTING TEST STRIP	EACH	1	1.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	347	347
40600990	TEMPORARY RAMP	SQ YD	58	58
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	5,892	5,892
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	115	115
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	71,603	71,603
44200132	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	976	976
44200136	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	224	224
44200138	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	187	187
48101200	AGGREGATE SHOULDERS, TYPE B	TON	891	891
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	20,647	20,647
64200105	SHOULDER RUMBLE STRIP	FT	48,652	48,652
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6.0

* (108x,130,102)RS-3; 129RS-4, 101RS-2

FILE NAME = 68890-resurfacing.dgn	USER NAME = bogertmj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	F.A.P. RTE. 22	SECTION -	COUNTY PEORIA	TOTAL SHEETS 100	SHEET NO. 52
PLOT SCALE = 200.0000' / IN.		CHECKED -	REVISED -							CONTRACT NO. 68890		
PLOT DATE = 4/7/2009		DATE -	REVISED -	ILLINOIS FED. AID PROJECT								