

MATERIAL TRANSFER DEVICE	TON
TOTAL	5,892

CHANGEABLE MESSAGE SIGN	CAL MO
TOTAL	1

TRAFFIC CONTROL SURVEILLANCE	CAL DA
TOTAL	20

CLASS D PATCHES, 11 INCH			
	Type II	Type III	Type IV
LOCATION	SQ YD	SQ YD	SQ YD
PATCHING UNIT 1	218.67	0.00	106.67
PATCHING UNIT 2	96.00	0.00	0.00
PATCHING UNIT 3	357.33	96.00	26.67
PATCHING UNIT 4	304.00	128.00	53.33
TOTAL	976	224	187

STATION TO STATION	LENGTH FEET	EPOXY PAVEMENT MARKING (FEET)			TEMPORARY PAVEMENT MARKING (FEET)			SHORT TERM PAVT MARKING* (FEET)	WORK ZONE PAVT MARKING REMOVAL (SQ. FT.)
		4"			4"				
		SOLID		SK. D.	SOLID		SK.D.		
		W	Y	Y	W	Y	Y	Y	
STA. 459+18 to 463+73	455	910	910	0	910	910	0	46	15
STA. 463+73 to 485+43	2170	4340	2170	543	4340	2170	543	217	72
STA. 485+43 to 493+87	844	1688	0	211	1688	0	211	84	28
BRIDGE OMISSION									
STA. 497+97 to 508+38	1041	2082	1041	260	2082	1041	260	104	35
STA. 508+38 to 513+42	504	1008	1008	0	1008	1008	0	50	17
STA. 513+42 to 518+78	536	1072	1072	134	1072	1072	134	54	18
STA. 518+78 to 542+27	2349	4698	0	587	4698	0	587	235	78
STA. 542+27 to 558+65	1638	3276	1638	410	3276	1638	410	164	55
STA. 558+65 to 649+33	9068	18136	0	2267	18136	0	2267	907	302
STA. 649+33 to 653+00	367	734	367	92	734	367	92	37	12
STA. 653+00 to 664+18	1118	2236	2236	0	2236	2236	0	112	37
STA. 664+18 to 669+38	520	1040	520	130	1040	520	130	52	17
STA. 669+38 to 713+29	4391	8782	0	1098	8782	0	1098	439	146
STA. 713+29 to 719+30	601	1202	601	150	1202	601	150	60	20
SUB TOTAL		51204	11563	5881	51204	11563	5881	2560	853
SUB TOTAL		51204	17444		51204	17444		X 2 APP.	
GRAND TOTAL		68649			68649			5120	853

* (108x,130,102)RS-3; 129RS-4, 101RS-2

FILE NAME = 68890-resur-facing.dgn	USER NAME = boyer.m.j	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCALE: SHEET NO. OF SHEETS STA. TO STA.	F.A.P. RTE. 22	SECTION	COUNTY PEORIA	TOTAL SHEETS 100	SHEET NO. 57
PLOT SCALE = 200.0000 "/>										