

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72		**	104	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

\* 74(10-70)RS-3 & (10-71,73)RS-2  
 \*\* PIATT & CHAMPAIGN

# SUMMARY OF QUANTITIES

CODE NO	ITEM	CONSTRUCTION TYPE CODE:	UNIT	TOTAL QUANTITY	PIATT COUNTY		CHAMPAIGN COUNTY		CHAMPAIGN COUNTY		CHAMPAIGN COUNTY		CHAMPAIGN COUNTY	
					100% STATE QUANTITY	100% STATE QUANTITY	100% STATE QUANTITY	100% STATE QUANTITY	100% STATE QUANTITY	100% STATE QUANTITY	100% STATE QUANTITY	100% STATE QUANTITY		
20400800	FURNISHED EXCAVATION		CU YD	428.0	41.0		74.0		311.0					
* 25000210	SEEDING, CLASS 2A		ACRE	0.8	0.1		0.1		0.6					
* 25000400	NITROGEN FERTILIZER NUTRIENT		POUND	67.5	6.0		12.0		49.5					
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT		POUND	67.5	6.0		12.0		49.5					
* 25000600	POTASSIUM FERTILIZER NUTRIENT		POUND	67.5	6.0		12.0		49.5					
* 25100115	MULCH, METHOD 2		ACRE	0.8	0.1		0.1		0.6					
* 28000250	TEMPORARY EROSION CONTROL SEEDING		POUND	75.0	7.0		13.0		55.0					
35101400	AGGREGATE BASE COURSE, TYPE B		TON	20.8					20.8					
40600100	BITUMINOUS MATERIALS (PRIME COAT)		GALLON	60,198	11,609.0		20,464		27,767	70.0		74.0		214.0
40600300	AGGREGATE (PRIME COAT)		TON	1,205	233.0		411.0		561					
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90		TON	660	138.0		247		275.0					
40600895	CONSTRUCTING TEST STRIP		EACH	3.0	1.5		1.5							
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT		SQ YD	2,700	567.0		999.0		1,134.0					
40600990	TEMPORARY RAMP		SQ YD	6,000.0	1,253.0		2,227.0		2,520.0					
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER, IL 19.0, N90		TON	44,520	8,121.0		14,308.0		22,091					
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90		TON	32,971	6,061.0		10,684		15,865	59.0		62.0		240.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)		GALLON	136.0	68.0		68.0							
40800030	AGGREGATE (PRIME COAT)		TON	3.0	1.5		1.5							
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING		TON	153.0	76.5		76.5							
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"		SQ YD	17,285.0	576.0		1,025.0		15,684.0					

(CONTD NEXT SHEET)

\* SPECIALTY ITEM

SHEET 1 OF 6

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 F.A.I. ROUTE 72  
 SECTION 74(10-70)RS-3&(10-71,73)RS-2  
 PIATT & CHAMPAIGN CO.  
 SCALE: N/A  
 DATE: 04-01-09  
 DRAWN BY: JMS  
 CHECKED BY:

PLOT DATE = 4/17/2009  
 FILE NAME = c:\nsp\as-a\p\1001\BLACKRT\08112945.0578025-ah-500.dgn  
 PLOT SCALE = 100-3004 / IN.  
 USER NAME = b100000