

# GUARDRAIL SCHEDULES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	**	104	32

\*74(10-70)RS-3 & (10-71,73)RS-2  
\*\* CHAMPAIGN & PIATT

## 074-0007

### 63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH(FT)
1420+33.00		1422+21.00	EB RT 188.00
1421+03.00		1422+95.00	WB RT 192.00

### 63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH
1419+13.12		1419+63.12	EB RT 1.0
1423+60.42		1424+10.42	WB RT 1.0

### 63000001 STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS

STATION	TO	STATION	LENGTH(FT)
1419+63.12		1421+63.12	EB RT 200.00
1421+60.42		1423+60.42	WB RT 200.00

### 63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION	TO	STATION	EACH
1421+63.12		1422+21.27	EB RT 1.0
1421+02.27		1421+60.42	WB RT 1.0

### 78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH
1419+21.27	EB RT 1.0
1424+10.42	WB RT 1.0

## 010-0205 (EB) & 010-0206 (WB)

### 63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH(FT)
1606+81.00		1610+15.00	EB RT 334.00
1608+40.00		1610+03.00	EB LT 163.00
1610+51.00		1613+77.00	WB RT 326.00
1610+55.00		1612+18.00	WB LT 163.00

### 63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH
1607+11.85		1607+61.85	EB RT 1.0
1606+12.35		1606+62.35	EB LT 1.0
1613+04.15		1613+54.15	WB RT 1.0
1613+95.65		1614+45.65	WB LT 1.0

### 63000001 STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS

STATION	TO	STATION	LENGTH(FT)
1607+61.85		1609+61.85	EB RT 200.00
1606+62.35		1609+49.85	EB LT 287.50
1611+04.15		1613+04.15	WB RT 200.00
1611+08.15		1613+95.65	WB LT 287.50

### 63100085 TRAFFIC BARRIER TERMINAL TYPE 6

STATION	TO	STATION	EACH
1609+61.85		1610+07.50	EB RT 1.0
1609+49.85		1609+95.50	EB LT 1.0
1610+58.50		1611+04.15	WB RT 1.0
1610+62.50		1611+08.15	WB LT 1.0

### 78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH
1607+11.85	EB RT 1.0
1606+12.35	EB LT 1.0
1613+54.15	WB RT 1.0
1614+45.65	WB LT 1.0

## 010-0160

### 63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH(FT)
1617+60.00		1621+86.00	EB RT 426.00
1620+67.00		1624+04.00	WB RT 337.00

### 63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH
1617+72.08		1618+22.08	EB RT 1.0
1623+23.36		1623+73.36	WB RT 1.0

### 63000001 STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS

STATION	TO	STATION	LENGTH(FT)
1618+22.08		1620+22.08	EB RT 200.00
1621+24.41		1621+99.41	EB RT 75.00
1621+23.36		1623+23.36	WB RT 200.00

### Z0026260 FURNISHING AND INSTALLING TUBULAR THRIE BEAM

STATION	TO	STATION	LENGTH(FT)
1620+65.83		1620+81.00	EB RT 15.00

### 63100217 TRAFFIC BARRIER TERMINAL TYPE 6B (SPECIAL)

STATION	TO	STATION	EACH
1620+22.08		1620+65.83	EB RT 1.0
1620+81.00		1621+24.75	EB RT 1.0
1620+67.21		1621+23.36	WB RT 1.0

### 63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION	TO	STATION	EACH
1621+99.41		1622+13.68	EB RT 1.0

### 78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH
1419+21.27	EB RT 1.0
1424+10.42	WB RT 1.0

## 010-0056

### 63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH(FT)
1672+43.00		1674+30.00	EB RT 187.00
1674+14.00		1676+01.00	WB RT 187.00

### 63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH
1671+19.82		1671+69.82	EB RT 1.0
1676+56.00		1678+06.00	WB RT 1.0

### 63000001 STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS

STATION	TO	STATION	LENGTH(FT)
1671+69.82		1673+69.82	EB RT 200.00
1674+56.00		1676+56.00	WB RT 200.00

### 63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION	TO	STATION	EACH
1673+69.82		1674+27.97	EB RT 1.0
1673+97.85		1674+56.00	WB RT 1.0

### 78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH
1671+19.85	EB RT 1.0
1678+06.00	WB RT 1.0

## 010-0146

### 63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH(FT)
1778+53.00		1780+17.00	EB RT 164.00
1780+02.00		1781+52.00	WB RT 123.00

### 63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH
1777+06.96		1777+56.96	EB RT 1.0
1782+62.44		1783+12.44	WB RT 1.0

### 63000001 STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS

STATION	TO	STATION	LENGTH(FT)
1777+56.96		1779+56.96	EB RT 200.00
1780+62.44		1782+62.44	WB RT 200.00

### 63100217 TRAFFIC BARRIER TERMINAL TYPE 6B (SPECIAL)

STATION	TO	STATION	EACH
1779+56.96		1780+13.61	EB RT 1.0
1780+05.79		1780+62.44	WB RT 1.0

### 78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH
1777+06.96	EB RT 1.0
1783+12.44	WB RT 1.0

## 010-0203 (EB) & 010-0204 (WB)

### 63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH(FT)
1837+39.00		1840+65.00	EB RT 326.00
1838+93.00		1840+57.00	EB LT 164.00
1841+19.00		1844+32.00	WB RT 313.00
1841+16.00		1842+79.00	WB LT 163.00

### 63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH
1837+58.85		1838+08.85	EB RT 1.0
1836+63.35		1837+13.35	EB LT 1.0
1843+75.15		1844+25.15	WB RT 1.0
1844+59.65		1845+09.65	WB LT 1.0

### 63000001 STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS

STATION	TO	STATION	LENGTH(FT)
1838+08.85		1840+08.85	EB RT 200.00
1837+13.35		1840+00.85	EB LT 287.50
1841+75.15		1843+75.15	WB RT 200.00
1841+72.15		1844+59.65	WB LT 287.50

### 63100085 TRAFFIC BARRIER TERMINAL TYPE 6

STATION	TO	STATION	EACH
1840+08.85		1840+54.50	EB RT 1.0
1840+00.85		1840+46.50	EB LT 1.0
1841+29.50		1841+75.15	WB RT 1.0
1841+26.50		1841+72.15	WB LT 1.0

### 78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH
1837+58.85	EB RT 1.0
1836+63.35	EB LT 1.0
1844+25.15	WB RT 1.0
1845+09.65	WB LT 1.0

### ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72  
SECTION 74(10-70)RS-3 & (10-71,73)RS-2  
CHAMPAIGN & PIATT COUNTY

SCALE: NONE DRAWN BY: MLB  
DATE: 04/01/2009 CHECKED BY:

PLOT DATE = 4/13/2009  
FILE NAME = c:\p\m\work\PIATT\SHERER\JM\0112945\70025 Schedules.dgn  
PLOT SCALE = 4.23629 / IN.  
USER NAME = sherer\_jm