## CLASS A PATCHING, 13" (CONT'D)

## **PATCH AREA**

			LENGTH	WIDTH	X4420046 TYPE II 14.0"	X4420064 TYPE III 14.0"	X4420066 TYPE IV 14.0"	44213200 SAW CUTS	Z0075300 TIE BARS	44213000 PATCHING REINFORCEMENT
STATION	DIRECTION	LANE	<u>(ft)</u>	(ft)	(sq. yd)	(sq. yd)	(sq. yd)	(ft)	(each)	<u>(sq. yd)</u>
1674+40.00	ЕВ	DL	10	12	13.3	0.0	0.0	68.0	0	13.3
1680+07.00	EB	DL	8	12	10.7	0.0	0.0	64.0	0	10.7
1698+27.00	EB	PL	10	12	13.3	0.0	0.0	68.0	0	13.3
1698+27.00	EB	DL	16	12	0.0	21.3	0.0	80.0	0	21.3
1699+00.00	EB	DL	18	12	0.0	24.0	0.0	84.0	0	24.0
1700+23.00	EB	DL	6	12	8.0	0.0	0.0	60.0	0	8.0
1700+39.00	EB	DL	8	12	10.7	0.0	0.0	64.0	0	10.7
1701+52.00	EB	DL	6	12	8.0	0.0	0.0	60.0	0	8.0
1703+24.00	EB	PL	12	12	0.0	16.0	0.0	72.0	0	16.0
1703+24.00	EB	DL	20	12	0.0	0.0	26.7	88.0	10	26.7
1703+53.00	EB	DL	6	12	8.0	0.0	0.0	60.0	0	8.0
1704+72.00	EB	DL	6	12	8.0	0.0	0.0	60.0	0	8.0
1706+32.00	EB	DL	8	12	10.7	0.0	0.0	64.0	0	10.7
1707+56.00	EB	DL	8	12	10.7	0.0	0.0	64.0	0	10.7
1709+61.00	EB	DL	8	12	10.7	0.0	0.0	64.0	0	10.7
1710+80.00	EB	PL	20	12	0.0	0.0	26.7	88.0	10	26.7
1710+80.00	EB	DL	20	12	0.0	0.0	26.7	88.0	10	26.7
1711+14.00	EB	DL	24	12	0.0	0.0	32.0	96.0	12	32.0
1712+34.00	EB	DL	10	12	13.3	0.0	0.0	68.0	0	13.3
1713+17.00	EB	DL	6	12	8.0	0.0	0.0	60.0	0	8.0
1719+43.00	EB	DL	6	12	8.0	0.0	0.0	60.0	0	8.0
1721+18.00	EB	DL	6	12	8.0	0.0	0.0	60.0	0	8.0
1723+20.00	EB	DL	12	12	0.0	16.0	0.0	72.0	0	16.0
1723+71.00	EB	DL	14	12	0.0	18.7	0.0	76.0	0	18.7
1727+49.00	EB	DL	6	12	8.0	0.0	0.0	60.0	0	8.0
1729+35.00	EB	DL	6	12	8.0	0.0	0.0	60.0	0	8.0
1732+59.00	EB	DL	24	6	0.0	16.0	0.0	72.0	12	16.0
1733+07.00	EB	DL	6	12	8.0	0.0	0.0	60.0	0	8.0
1735+17.00	EB	DL	6	12	8.0	0.0	0.0	60.0	0	8.0
1738+15.00	EB	DL	8	12	10.7	0.0	0.0	64.0	0	10.7
				SUB-TOTAL =	192.0	112.0	112.0	2064.0	54.0	<b>416.</b> 0

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72 SECTION 74(10-70)RS-3 & (10-71,73)RS-2 CHAMPAIGN & PIATT COUNTY

SCALE: NONE DATE: 04/01/2009 DRAWN BY: MLB CHECKED BY