CONTRACT NO. 70508

F.A.P. RTE.	SECTION		TOTAL SHEETS	SHEET NO.
709	(104)RS-1	MCLEAN	21	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

PAGE 1 OF 2

LOCATION OF WORK: MCLEAN COUNTY
RURAL
FAP 709 (US 136)

STA. 1162+80.00
STA. 1450+95.00

FUNDING BREAKOUT: 100% STATE

CONSTRUCTION TYPE CODE: I000

CODE NO	ITEM	UNIT	TOTAL QUANTITY
20400800	FURNISHED EXCAVATION	CU YD	4.0
20900110	POROUS GRANULAR BACKFILL	CU YD	8.0
25100630	EROSION CONTROL BLANKET	SQ YD	12.0
35101400	AGGREGATE BASE COURSE, TYPE B	TON	48.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	7,614.0
40600300	AGGREGATE (PRIME COAT)	TON	154.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600990	TEMPORARY RAMP	SQ YD	226.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	6,395.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	184.0
40800030	AGGREGATE (PRIME COAT)	TON	4.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	155.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	76,124.0
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	1,715.0
44000100	PAVEMENT REMOVAL	SQ YD	125.0
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	51.0
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	52.0
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	114.0

*SPECIALTY ITEMS

PLOT DATE = 3/25/2009
FILE NAME = C:\pwworking\PWIDOT\AUSTINRL\d0128975\70508plan.dgn
PLOT SCALE = 42.3529 ' / IN.
USER NAME = austinrl