

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
709	1104RS-1	MCLEAN	21	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

LOCATION OF WORK: **MCLEAN COUNTY RURAL**
FAP 709 (US 136)
STA. 1162+80.00
STA. 1450+95.00

SUMMARY OF QUANTITIES
PAGE 2 OF 2

FUNDING BREAKOUT: **100% STATE**
 CONSTRUCTION TYPE CODE: **I000**

CODE NO	ITEM	UNIT	TOTAL QUANTITY
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,196.0
50105220	PIPE CULVERT REMOVAL	FOOT	40.0
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2.0
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	40.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2.0
67100100	MOBILIZATION	L SUM	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5,192.0
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	123.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	72,619.0
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	72.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	859.0
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	123.0
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	72.0
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	72,619.0
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	372.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	361.0
X0301232	SURVEY MARKER VAULT	EACH	8.0
X4401705	PARTIAL DEPTH REMOVAL	SQ YD	780.0
X4421000	PARTIAL DEPTH PATCHING	TON	241.0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0

*SPECIALTY ITEMS

PLOT DATE = 3/25/2009
 FILE NAME = \\P:\PROJECTS\70508\70508.dgn
 PLOT SCALE = 42.3529 / IN.
 USER NAME = austinr1