

CODE NO	ITEM	UNIT	TOTAL QUANTITY FAI - RURAL MULTILANE 100% STATE X081-2A
20200100	EARTH EXCAVATION	CU YD	25.0
20400800	FURNISHED EXCAVATION	CU YD	33.0
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	216.0
20800150	TRENCH BACKFILL	CU YD	11.0
*25000210	SEEDING, CLASS 2A	ACRE	0.25
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23.0
*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23.0
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23.0
25100630	EROSION CONTROL BLANKET	SO YD	1,210.0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	25.0
28000400	PERIMETER EROSION BARRIER	FOOT	630.0
28000500	INLET AND PIPE PROTECTION	EACH	1.0
28100107	STONE RIPRAP, CLASS A4	SO YD	1,102.0
28200200	FILTER FABRIC	SO YD	1,102.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	52.0
40600990	TEMPORARY RAMP	SO YD	107.0
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	18.0
42001300	PROTECTIVE COAT	SO YD	276.0
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SO YD	276.0
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	145.0
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	233.0
44000700	APPROACH SLAB REMOVAL	SO YD	238.0
44004250	PAVED SHOULDER REMOVAL	SO YD	162.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	10.0
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1.0
50102400	CONCRETE REMOVAL	CU YD	47.4
50104400	CONCRETE HEADWALL REMOVAL	EACH	1.0
50104650	SLOPE WALL REMOVAL	SO YD	794.0
50105220	PIPE CULVERT REMOVAL	FOOT	101.0
50200100	STRUCTURE EXCAVATION	CU YD	222.0
50300225	CONCRETE STRUCTURES	CU YD	31.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	194.1
50300260	BRIDGE DECK GROOVING	SO YD	462.0
50300300	PROTECTIVE COAT	SO YD	574.0
50400805	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 36 IN.	FOOT	623.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	45,120.0
50800515	BAR SPLICERS	EACH	488.0
51205200	TEMPORARY SHEET PILING	SO FT	400.0
51500100	NAME PLATES	EACH	1.0
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12.0

*SPECIALTY ITEM
*SFTY 3N

CODE NO	ITEM	UNIT	TOTAL QUANTITY FAI - RURAL MULTILANE 100% STATE X081-2A
52100520	ANCHOR BOLTS, 1"	EACH	24.0
52100540	ANCHOR BOLTS, 1 1/2"	EACH	4.0
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1.0
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	101.0
59000200	EPOXY CRACK INJECTION	FOOT	51.0
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	103.0
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	1.0
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	22.0
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	178.0
60262700	INLETS TO BE RECONSTRUCTED	EACH	1.0
*63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	350.0
*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2.0
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1.0
*63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	1.0
63200310	GUARDRAIL REMOVAL	FOOT	497.0
64200105	SHOULDER RUMBLE STRIP	FOOT	166.0
66500105	WOVEN WIRE FENCE, 4'	FOOT	68.0
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	89.0
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	6.0
67100100	MOBILIZATION	L SUM	1.0
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	1.0
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	45.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3,126.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2,688.0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	443.0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	418.0
*78000200	THERMOPLASTIC PAVEMENT MARKING- LINE 4"	FOOT	1,976.0
*78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	247.0
*78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	336.0
*78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	42.0
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4.0
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4.0
*78200405	GUARDRAIL MARKERS	EACH	8.0
*78200500	BARRIER WALL MARKERS	EACH	6.0
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2.0
78300100	PAVEMENT MARKING REMOVAL	SO FT	337.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8.0
X0323080	DRAINAGE SCUPPERS, DS-12	EACH	2.0
X0324865	DIAMOND GRINDING (BRIDGE SECTION)	SO YD	678.0

FILE NAME =	USER NAME = keysrb	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cl:\ph\work\PW1001\KEYSRB\0124831\057021.sht-500.DGN		DRAWN -	REVISED -		74	(57-22B-1)BR	MCLEAN	46	3				
PLOT SCALE = 100.0000 / IN.		CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 70721				
PLOT DATE = 3/20/2009		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								