

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

☉ ROADWAY, P.G. & STAGE CONST. LINE

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection and Grinding
Back of West Abut.	1126+76.21	0.00	772.92	772.94
☉ Brg. West Abut.	1126+79.21	0.00	772.94	772.96
A	1126+89.21	0.00	773.02	773.09
B	1126+99.21	0.00	773.09	773.19
C	1127+09.21	0.00	773.17	773.27
D	1127+19.21	0.00	773.25	773.32
W. ☉ Brg. Pier	1127+29.96	0.00	773.33	773.35
☉ Pier	1127+30.96	0.00	773.34	773.36
E. ☉ Brg. Pier	1127+31.96	0.00	773.34	773.36
E	1127+41.96	0.00	773.42	773.49
F	1127+51.96	0.00	773.50	773.60
G	1127+61.96	0.00	773.57	773.68
H	1127+71.96	0.00	773.65	773.73
☉ Brg. East Abut.	1127+82.71	0.00	773.73	773.75
Back of East Abut.	1127+85.71	0.00	773.76	773.78

BEAM 4

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection and Grinding
Back of West Abut.	1126+75.60	1.60	772.89	772.91
☉ Brg. West Abut.	1126+78.60	1.60	772.91	772.93
A	1126+88.60	1.60	772.99	773.06
B	1126+98.60	1.60	773.06	773.16
C	1127+08.60	1.60	773.14	773.24
D	1127+18.60	1.60	773.22	773.29
W. ☉ Brg. Pier	1127+29.35	1.60	773.30	773.32
☉ Pier	1127+30.35	1.60	773.31	773.33
E. ☉ Brg. Pier	1127+31.35	1.60	773.31	773.33
E	1127+41.35	1.60	773.39	773.46
F	1127+51.35	1.60	773.47	773.57
G	1127+61.35	1.60	773.54	773.65
H	1127+71.35	1.60	773.62	773.70
☉ Brg. East Abut.	1127+82.10	1.60	773.70	773.72
Back of East Abut.	1127+85.10	1.60	773.73	773.75

BEAM 5

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection and Grinding
Back of West Abut.	1126+72.83	8.81	772.75	772.77
☉ Brg. West Abut.	1126+75.83	8.81	772.77	772.79
A	1126+85.83	8.81	772.85	772.92
B	1126+95.83	8.81	772.93	773.03
C	1127+05.83	8.81	773.01	773.11
D	1127+15.83	8.81	773.08	773.16
W. ☉ Brg. Pier	1127+26.58	8.81	773.16	773.18
☉ Pier	1127+27.58	8.81	773.17	773.19
E. ☉ Brg. Pier	1127+28.58	8.81	773.18	773.20
E	1127+38.58	8.81	773.26	773.33
F	1127+48.58	8.81	773.33	773.44
G	1127+58.58	8.81	773.41	773.52
H	1127+68.58	8.81	773.49	773.56
☉ Brg. East Abut.	1127+79.33	8.81	773.57	773.59
Back of East Abut.	1127+82.33	8.81	773.59	773.61

BEAM 6

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection and Grinding
Back of West Abut.	1126+70.06	16.02	772.60	772.62
☉ Brg. West Abut.	1126+73.06	16.02	772.62	772.64
A	1126+83.06	16.02	772.70	772.77
B	1126+93.06	16.02	772.77	772.88
C	1127+03.06	16.02	772.85	772.96
D	1127+13.06	16.02	772.93	773.01
W. ☉ Brg. Pier	1127+23.81	16.02	773.01	773.03
☉ Pier	1127+24.81	16.02	773.02	773.04
E. ☉ Brg. Pier	1127+25.81	16.02	773.02	773.04
E	1127+35.81	16.02	773.10	773.17
F	1127+45.81	16.02	773.18	773.28
G	1127+55.81	16.02	773.26	773.36
H	1127+65.81	16.02	773.33	773.41
☉ Brg. East Abut.	1127+76.56	16.02	773.41	773.43
Back of East Abut.	1127+79.56	16.02	773.44	773.46

TOP OF SLAB ELEVATIONS
STRUCTURE NO. 057-0129

SHEET NO. 4 26 SHEETS	F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	74	(57-22B-1)BR	Mc LEAN	46	14
			CONTRACT NO. 70721		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT		

THE UPCHURCH GROUP, INC.