

LOCATION OF WORK:

FAP 697  
IL. 9  
VERMILION CO.  
RURAL  
TWO LANE  
STA 417+78 TO  
STA. 1096+21.5  
100% STATE  
1000

FAP 697  
IL. 9  
VERMILION CO.  
URBAN  
TWO LANE  
STA 1097+45.5 TO  
STA 1207+00  
100% STATE  
1000

FUNDING BREAKOUT:  
CONSTRUCTION TYPE CODE:

CODE NO	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	39,840.0	36,239.0	3,601.0
40600300	AGGREGATE (PRIME COAT)	TON	798.0	726.0	72.0
40600625	LEVELING BINDER (MACHINE METHOD), N 50	TON	7,600.0	7,600.0	0.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0	0.0	1.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL- BUTT JOINT	SQ YD	3,067.0	3,067.0	0.0
40600990	TEMPORARY RAMP	SQ YD	359.0	171.0	188.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N 50	TON	15,200.0	15,200.0	0.0
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N 50	TON	2,878.0	0.0	2,878.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,000.0	592.0	408.0
40800030	AGGREGATE (PRIME COAT)	TON	20.0	12.0	8.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	839.0	497.0	342.0
44000085	HOT-MIX ASPHALT SURFACE REMOVAL (COLD MILL), SPECIAL	SQ YD	1,785.0	350.0	1,435.0
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	178,247.0	178,247.0	0.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	36,004.0	0.0	36,004.0
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	1,553.0	1,553.0	0.0
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	5,065.0	0.0	5,065.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5,270.0	5,250.0	20.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	195.0	48.0	147.0
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5.0	4.0	1.0
67100100	MOBILIZATION	L SUM	1.0	0.8	0.2
70100450	TRAFFIC CONTROL <sup>AND</sup> PROTECTION, STANDARD 701201	L SUM	1.0	1.0	0.0
70100460	TRAFFIC CONTROL <sup>AND</sup> PROTECTION, STANDARD 701306	L SUM	1.0	1.0	0.0
70102620	TRAFFIC CONTROL <sup>AND</sup> PROTECTION, STANDARD 701501	L SUM	1.0	0.0	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	23,960.0	18,820.0	5,140.0

FILE NAME =	USER NAME = ceo-lockjd	DESIGNED -	REVISED -
ca:\ph_work\PWIDOT\CEARLOCKJD\0115224\370764-500.dgn		DRAWN -	REVISED -
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 4/10/2009	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
697	2RS-3&4RS-8	Vermilion	43	4
CONTRACT NO. 70764			ILLINOIS FED. AID PROJECT	