

78000400 THERMOPLASTIC PAVEMENT MARKING LINE 6" - URBAN

USE FOR CROSSWALK AT 5TH STREET IN HOOPESTON

TOTAL= 112.0 FEET WHITE

78000600 THERMOPLASTIC PAVEMENT MARKING LINE 12" - URBAN

STATION	TO	STATION	LOCATION	QUANTITY (FT)	COLOR
1098+80		1100+76	MEDIAN	45.0	YELLOW
1101+26		1105+60	MEDIAN	108.0	YELLOW
1106+42		1109+80	MEDIAN	72.0	YELLOW
1111+52		1113+77	MEDIAN	50.0	YELLOW

TOTAL= 275.0 FEET

78000650 THERMOPLASTIC PAVEMENT MARKING LINE 24" - URBAN

STATION	LOCATION	QUANTITY (FT)	COLOR
1105+57	STOP BAR	12.0	WHITE
1105+75	STOP BAR	13.5	WHITE
1106+27	STOP BAR	13.5	WHITE
1106+42	STOP BAR	12.0	WHITE
EB	RR STOP BARS	42.0	WHITE
WB	RR STOP BARS	42.0	WHITE
5TH ST.	MEDIAN	17.0	WHITE

TOTAL= 152.0

78001110 PAINT PAVEMENT MARKING LINE 4" - RURAL

STATION	TO	STATION	LOCATION	QUANTITY (FT)	COLOR
LT/RT 417+78		LT/RT 1096+22	EDGE LINE	133,155.0	WHITE
C/L 417+78		C/L 1096+22	SKIP-DASH	16,880.0	YELLOW
RT 553+93		RT 559+21	NO PASSING	528.0	YELLOW
LT 565+55		LT 570+83	NO PASSING	528.0	YELLOW
RT 643+83		RT 649+11	NO PASSING	528.0	YELLOW
LT 657+84		LT 663+12	NO PASSING	528.0	YELLOW
RT 692+55		RT 697+83	NO PASSING	528.0	YELLOW
LT 703+60		LT 715+48	NO PASSING	1,188.0	YELLOW
RT 758+33		RT 763+61	NO PASSING	528.0	YELLOW
LT 772+72		LT 778+00	NO PASSING	528.0	YELLOW
RT 775+35		RT 781+35	NO PASSING	600.0	YELLOW
LT 785+58		LT 794+38	NO PASSING	880.0	YELLOW
RT 1057+70		RT 1062+98	NO PASSING	528.0	YELLOW
LT 1066+70		LT 1072+50	NO PASSING	580.0	YELLOW
LT/RT 1096+22		LT/RT 1097+46	EDGE LINE	248.0	WHITE
C/L 1096+22		C/L 1097+46	SKIP-DASH	30.0	YELLOW

TOTAL= 157,785.0 FEET

78001180 PAINT PAVEMENT MARKING 24" - RURAL

STATION	LOCATION	QUANTITY (FT)	COLOR
EAST LYNN RD NORTH	STOP BAR	20.0	WHITE
EAST LYNN RD SOUTH	STOP BAR	20.0	WHITE
TOTAL=		40.0	FEET

Z0055600 RUMBLE STRIPS - RURAL

STATION	LENGTH	WIDTH	QUANT.	AREA (SQ. YD.)
IL 9/ IL 49 INTERSECTION				
EAST BOUND	25.0	12.0	3.0	100.00
WEST BOUND	25.0	12.0	3.0	100.00
TOTAL=			200.0	

Z0070100 SURVEY MONUMENT COVER ASSEMBLY - RURAL					
STATION	OFFSET (Ft)			QUANTITY (EACH)	REMARKS
	LT.	C/L	RT.		
418+36.5	3.80			1.0	70E (Co. Line)
469+96		C/L		1.0	170E
496+31.7		C/L		1.0	W. of IL 49
607+30	3.05			1.0	
633+46			0.75	1.0	470E
659+70			10.50	1.0	
680+18.5	1.04			1.0	
684+17		C/L		1.0	
685+21			24.75	1.0	570E (in SR Return)
694+00		C/L		1.0	~240' E. of RR OH
738+90			4.00	1.0	670E
790+86.5		C/L		1.0	770E (E. Lynn Rd.)
884+39.25		C/L		1.0	PC
893+90.76		C/L		1.0	PT
897+16.33		C/L		1.0	PC (E. of 990E)
907+08.75		C/L		1.0	PT & Sta. Eqn.
918+95	0.60			1.0	
944+71.2	3.00			1.0	
970+69.75	2.50			1.0	1130E
996+55.5			0.50	1.0	
1073+98.5	1.20			1.0	

RURAL TOTAL= 21.0 EACH

Z0070100 SURVEY MONUMENT COVER ASSEMBLY - URBAN					
STATION	OFFSET (Ft)			QUANTITY (EACH)	REMARKS
	LT.	C/L	RT.		
1125+18		C/L		1.0	6th Avenue
1153+12.4		C/L		1.0	E of CSX RR
1179+63.5		C/L		1.0	1550E

URBAN TOTAL= 3.0 EACH

JOB TOTAL= 24.0 EACH