

SCHEDULE OF QUANTITIES

PAINT PAVEMENT MARKING - LINE

TERMINAL MARKER - DIRECT APPLIED

| LOCATION | QUANTITY (EACH) |
|---|--------------------|
| F. A. P. 317 (US 24) | |
| (STA. EQN #1) | |
| STA. 1140+13.58 (BK) = STA. 0+00.00 (AH) | |
| STA. 71+89.00 LT | 1 |
| STA. 72+28.00 RT | 1 |
| STA. 74+39.00 LT | 1 |
| STA. 75+03.00 RT | 1 |
| | |
| STA. 90+96.00 LT | 1 |
| STA. 90+96.00 RT | 1 |
| STA. 92+96.00 LT | 1 |
| STA. 92+96.00 RT | 1 |
| | |
| STA. 137+52.00 RT | 1 |
| STA. 137+83.00 LT | 1 |
| STA. 140+83.00 LT | 1 |
| STA. 141+02.00 RT | 1 |
| | |
| (STA. EQN #2) | |
| STA. 143+62.01 (BK) = STA. 130+24.57 (AH) | |
| | |
| PROJECT TOTAL | 12 |

| LOCATION | 5" | | | |
|---|---------------------|-----------------|------------------------------|-----------------|
| | YELLOW | | | WHITE |
| | DBL-SOLID (FOOT) | SOLID (FOOT) | SKIP-DASH (FOOT) | SOLID (FOOT) |
| F. A. P. 317 (US 24) | | | | |
| STA. 1150+07.50 TO STA. 1140+13.58 | - | - | - | 1,987.84 |
| STA. 1150+07.50 TO STA. 1145+00.00 | - | 507.50 | 126.88 | - |
| STA. 1145+00.00 TO STA. 1140+13.58 | 972.84 | - | - | - |
| (STA. EQN #1) | | | | |
| STA. 1140+13.58 (BK) = STA. 0+00.00 (AH) | | | | |
| STA. 0+00 TO STA. 4+00.00 | - | 400.00 | - | - |
| STA. 0+00 TO STA. 8+50.00 | - | - | 212.50 | - |
| STA. 0+00 TO STA. 143+62.01 | - | - | - | 28,724.02 |
| STA. 5+50.00 TO STA. 8+50.00 | - | 300.00 | - | - |
| STA. 8+50.00 TO STA. 18+40.00 | 1,980.00 | - | - | - |
| STA. 18+40.00 TO STA. 29+50.00 | - | 1,110.00 | - | - |
| STA. 30+00.00 TO STA. 45+50.00 | - | 1,550.00 | - | - |
| STA. 18+40.00 TO STA. 81+50.00 | - | - | 1,577.50 | - |
| STA. 74+80.00 TO STA. 81+50.00 | - | 670.00 | - | - |
| STA. 81+50.00 TO STA. 88+00.00 | 1,300.00 | - | - | - |
| STA. 88+00.00 TO STA. 93+80.00 | - | 580.00 | - | - |
| STA. 88+00.00 TO STA. 143+62.01 | - | - | 1,390.50 | - |
| STA. 132+50.00 TO STA. 143+62.01 | - | 1,112.01 | - | - |
| (STA. EQN #2) | | | | |
| STA. 143+62.01 (BK) = STA. 130+24.57 (AH) | | | | |
| STA. 130+24.57 TO STA. 131+75.00 | - | 150.43 | 37.61 | - |
| STA. 130+24.57 TO STA. 140+64.00 | - | - | - | 2,078.86 |
| STA. 132+75.00 TO STA. 140+64.00 | 1,578.00 | - | - | - |
| | | | | |
| (W. MAIN ST. - STA. 51+60.09 LT @ Mainline) | | | | |
| STA. 10+14.49 TO STA. 11+10.62 | 192.26 | - | - | - |
| S. E. QUADRANT | | | (Measured Using CADD) 125.84 | |
| S. W. QUADRANT | | | (Measured Using CADD) 97.20 | |
| | | | | |
| (MAIN ST. - STA. 125+00.09 LT @ Mainline) | | | | |
| STA. 10+13.21 TO STA. 10+98.74 | 171.06 | - | - | - |
| S. E. QUADRANT | | | (Measured Using CADD) 101.81 | |
| S. W. QUADRANT | | | (Measured Using CADD) 97.91 | |
| | | | | |
| SUBTRACT | | | | |
| (10 SIDE ROADS) (APPROX. 30' EA) | | | | |
| - | | | | |
| | | | | |
| SUBTOTALS | | | | |
| | 6,194.16 | 6,379.94 | 3,344.99 | 32,913.48 |
| | | | | |
| PROJECT TOTAL | | | | |
| | | 48,833 | | |

| | | | |
|-------------|-------------------|----------------|-----------|
| FILE NAME = | USER NAME = coxjw | DESIGNED - JWC | REVISED - |
| | | DRAWN - JWC | REVISED - |
| | | CHECKED - RSC | REVISED - |
| | | DATE - | REVISED - |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: 50 SHEET NO. 4 OF 6 SHEETS STA. TO STA.

| | | | | |
|---|---------------------------------|-----------------|--------------------|-----------------|
| F.A.P. RTE. 317 | SECTION (3,4)RS-6; (5,6)RS-4 | COUNTY Adams | TOTAL SHEETS 10 | SHEET NO. 11 |
| CONTRACT N. 72845 | | | | |
| FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT | | | | |