

MAINLINE PAVEMENT MARKING SCHEDULE (CONT.)

WESTBOUND LANE PAVEMENT MARKING

LOCATION STATION TO STATION	PREFORMED		THERMOPLASTIC		PERFORMED		SHORT TERM PAVEMENT MARKING (WHITE)		RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS		WORK ZONE PAVEMENT MARKING REMOVAL	NOTES
	LINE 6"		LINE 4"		LINE 8" (ON RAMPS)		MAINLINE SKIP-DASH	SHLDR. SKIP-DASH		CRYSTAL	AMBER		
	WHITE (SKIP-DASH)		SOLID WHITE (LT EP)	SOLID YELLOW (RT EP)	SOLID WHITE	SOLID YELLOW							
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT		EACH	EACH		
Westbound Lanes Centerline													
3003+41.0 TO 3148+78.1	3634		14537				1163	2190	183	183		7168	Rt. EP and Centerline NB Lanes
3003+41.0 TO 3004+16.0		75											Lt. EP
3016+37.0 TO 3034+17.0		1780											Lt. EP
3040+73.0 TO 3148+78.1		10805											Lt. EP
EQ. STA. 3148+78.1 (BK.) = STA. 3150+00.0 (AH.)													
3150+00.0 TO 3202+70.0	1318		5270				422	763	67	67		2588	Rt. EP and Centerline NB Lanes
3150+00.0 TO 3177+08.0		2708											Lt. EP
3188+39.0 TO 3199+85.0		1146											Lt. EP
S. N. 041-0082													
3204+27.0 TO 3220+87.0	415	1480	1660				133	266	22	22		1316	Lt. EP of Ramp A
S. N. 041-0084													
3222+37.0 TO 3314+91.0	2314	9254	9254				740	1480	117	117		7673	Along Gore for Ramp A Rt EP & Centerline Lt. EP of NB Lanes
Ramps													
3004+16.0 TO 3016+37.0		1221											RA Ent Ramp
3011+15.0 TO 3016+37.0				522									RA Ent Ramp
3011+15.0 TO 3014+57.0				342									RA Ent Ramp
3014+57.0 TO 3016+37.0					180								RA Ent Ramp
3034+17.0 TO 3040+73.0		656							52	52			RA Exit Ramp
3034+17.0 TO 3037+93.0				376									RA Exit Ramp
3034+67.0 TO 3037+93.0				326									RA Exit Ramp
3034+17.0 TO 3034+67.0					50				2		2		RA Exit Ramp
3177+08.0 TO 3188+39.0		1130											Lt. EP
3183+69.0 TO 3188+39.0				470									Ramp A
3183+69.0 TO 3186+58.0				289									Ramp A (skip-dash)
3186+58.0 TO 3188+39.0				181									Ramp A
3199+85.0 TO 3202+70.0		285							38	38			Ramp B
3204+27.0 TO 3206+07.0		180											Ramp B
3199+85.0 TO 3202+30.0				245									Ramp B
3204+27.0 TO 3206+07.0				180									Ramp B
3200+35.0 TO 3202+30.0				195									Ramp B
3199+85.0 TO 3200+35.0					50				2		2		Ramp B
WB TOTALS	7681	30,721	30,722	3,126	280	2458	4,699	483	479	483	4	18,746	
		61,443		3,406		7157							

TOTAL PAVEMENT MARKING QUANTITIES

LOCATION STATION TO STATION	PREFORMED		THERMOPLASTIC		PERFORMED		SHORT TERM PAVEMENT MARKING (WHITE)		RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS		WORK ZONE PAVEMENT MARKING REMOVAL	NOTES
	LINE 6"		LINE 4"		LINE 8" (ON RAMPS)		MAINLINE SKIP-DASH	SHLDR. SKIP-DASH		CRYSTAL	AMBER		
	WHITE (SKIP-DASH)		SOLID WHITE	SOLID YELLOW	SOLID WHITE	SOLID YELLOW							
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT		EACH	EACH		
TOTALS	15,361	61,438	61,441	4,560	380	4,916	9,496	925	919	6	37,035		
		122,879		4,940		14,412					925		

NOTES: TEMPORARY PAVEMENT MARKING QUANTITIES ARE CALCULATED FROM THE PERMANENT PAVEMENT MARKING.