

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	LOSEL, 01	LOSEL, 01	LOSEL, 02	LOSEL, 03	LOSEL, 04	LOSEL, 05	OTPOL, 01		
				CONSTRUCTION CODE FUNDS								
				80% FED 20% STATE ROADWAY 0004 URBAN	80% FED 20% STATE RETAINING WALL SN 022-W043 0040 URBAN	80% FED 20% STATE RETAINING WALL SN 022-W044 0040 URBAN	80% FED 20% STATE RETAINING WALL SN 022-W046 0040 URBAN	80% FED 20% STATE RETAINING WALL SN 022-W042 0040 URBAN	80% FED 20% STATE RETAINING WALL SN 022-W052 0040 URBAN	100% CITY OF NAPERVILLE ELECTRIC DUCT BANK 0043 URBAN		
20101200	TREE ROOT PRUNING	EACH	10								10	
20200100	EARTH EXCAVATION	CU YD	560	560								
20400800	FURNISHED EXCAVATION	CU YD	3785	3785								
20700220	POROUS GRANULAR EMBANKMENT	CU YD	56	56								
20800150	TRENCH BACKFILL	CU YD	1556	1556								
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	2280	2280								
25000210	SEEDING, CLASS 2A	ACRE	2.00	2.00								
25100115	MULCH, METHOD 2	ACRE	4.00	4.00								
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	1230	1230								
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	196	196								
28000305	TEMPORARY DITCH CHECKS	FOOT	30	30								
28000400	PERIMETER EROSION BARRIER	FOOT	2186	2186								
28000510	INLET FILTERS	EACH	39	39								
35501300	HOT-MIX ASPHALT BASE COURSE, 4"	SQ YD	37	37								
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	50	5							45	

X SPECIALTY ITEM

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
SCALE	SCALE	DRAWN	REVISED			338	2011-036-1	DUPAGE	234	4	
SCALE	SCALE	CHECKED	REVISED			SCALE: AS SHOWN SHEET NO. 1 OF 10 SHEETS STA. TO STA.					
SCALE	SCALE	DATE	REVISED			CONTRACT NO. 60P42 ILLINOIS FED. AID PROJECT					