

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE FUNDS							
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% CITY OF NAPERVILLE	
				ROADWAY 0004 URBAN	RETAINING WALL SN 022-W043 0040 URBAN	RETAINING WALL SN 022-W044 0040 URBAN	RETAINING WALL SN 022-W046 0040 URBAN	RETAINING WALL SN 022-W042 0040 URBAN	RETAINING WALL SN 022-W052 0040 URBAN	ELECTRIC DUCT BANK 0043 URBAN	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	995								995
44000100	PAVEMENT REMOVAL	SQ YD	493	43							450
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	45								45
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	296	82							214
44000600	SIDEWALK REMOVAL	SQ FT	995								995
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	20								20
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	140								140
50200100	STRUCTURE EXCAVATION	CU YD	1849		46	291	897	226	389		
50300225	CONCRETE STRUCTURES	CU YD	649.8		47.9	107.7	234.9	45.2	214.1		
50300285	FORM LINER TEXTURED SURFACE	SQ FT	8681			573	3264	339	4505		
50300300	PROTECTIVE COAT	SQ YD	1116		165	65	593	112	181		
50500505	STUD SHEAR CONNECTORS	EACH	1328				707	114	507		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	82820		7510	8690	29710	5190	31720		
50901720	BICYCLE RAILING	FOOT	622						622		

X SPECIALTY ITEM

FILE NAME	USER NAME - REGISTRATION	DESIGNED <i>NAV</i>	REVISED <i>06-04-12</i>	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
FILE #	FILE SCALE - SCALE #	DRAWN <i>KES</i>	REVISED			338	2011-036-1	DUPAGE	234	5	
	FILE DATE - DATE #	CHECKED <i>PJO</i>	REVISED			SCALE: AS SHOWN SHEET NO. 2 OF 10 SHEETS STA. TO STA.		CONTRACT NO. 60P42		ILLINOIS FED. AID PROJECT	
		DATE <i>05-11-12</i>	REVISED								