

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE FUNDS							
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% CITY OF NAPERVILLE	
				ROADWAY 0004 URBAN	RETAINING WALL SN 022-W043 0040 URBAN	RETAINING WALL SN 022-W044 0040 URBAN	RETAINING WALL SN 022-W046 0040 URBAN	RETAINING WALL SN 022-W042 0040 URBAN	RETAINING WALL SN 022-W052 0040 URBAN	ELECTRIC DUCT BANK 0043 URBAN	
50901750	PARAPET RAILING	FOOT	410		159	251					
51500100	NAME PLATES	EACH	5		1	1	1	1	1		
54010905	PRECAST CONCRETE BOX CULVERTS 9' X 5'	FOOT	24	24							
5421C030	PIPE CULVERTS, CLASS C, TYPE 1 30" (TEMPORARY)	FOOT	432	432							
5422C030	PIPE CULVERTS, CLASS C, TYPE 2 30" (TEMPORARY)	FOOT	68	68							
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	12	12							
550A0190	STORM SEWERS, CLASS A, TYPE 1 48"	FOOT	435	435							
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	8	8							
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	102	102							
550A0520	STORM SEWERS, CLASS A, TYPE 2 72"	FOOT	99	99							
550B0050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	154	154							
55100500	STORM SEWER REMOVAL 12"	FOOT	185	185							
55101400	STORM SEWER REMOVAL 30"	FOOT	566	566							
55102300	STORM SEWER REMOVAL 72"	FOOT	104	104							

X SPECIALTY ITEM

FILE NAME	USER NAME	DESIGNED	REVISED	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
FILE #		DRAWN	REVISED			338	2011-036-1	DUPAGE	234	6	
		CHECKED	REVISED			SCALE: AS SHOWN SHEET NO. 3 OF 10 SHEETS STA. TO STA.		CONTRACT NO. 60P42		ILLINOIS FED. AID PROJECT	
		DATE	REVISED								