

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE																
				A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q
				0004 URBAN	0021 URBAN	0014 URBAN	0040 URBAN	0040 URBAN	0040 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0028 URBAN	0028 URBAN	0043 URBAN	0021 URBAN	0028 URBAN	0028 URBAN
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	36	36																
40600895	CONSTRUCTING TEST STRIP	EACH	1	1																
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	36	36																
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	66	66																
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	97	97																
40701921	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12"	SQ YD	18912	18912																
40701961	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"	SQ YD	37406	37406																
42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SQ YD	97747	97747																
42001300	PROTECTIVE COAT	SQ YD	139371	139371																
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1286	1286																
42300600	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 10 INCH	SQ YD	2859	2859																

11

X SPECIALTY ITEM

- |  |  |   |
|--|--|---|
| A ROADWAY AND DRAINAGE - 80% FED, 20% STATE                      | H TRAFFIC SIGNALS - 80% FED, 10% STATE, 10% NAPERVILLE                         | O ROADWAY - 100% STATE                                      |
| B ROADWAY LIGHTING - 100% STATE                                  | I TRAFFIC SIGNALS AND LIGHTING - 100% NAPERVILLE                               | P SHARED-USE PATH - 80% STATE, 20% AURORA                   |
| C B.N.S.F. RR BRIDGE SN 022-0038 - 80% FED, 20% STATE            | J TRAFFIC SIGNAL INTERCONNECT / TEMPORARY TRAFFIC SIGNALS - 80% FED, 20% STATE | Q SHARED-USE PATH - 100% AURORA                             |
| D NOISE WALLS - 80% FED, 20% STATE                               | K SIDEWALK - 80% STATE, 20% NAPERVILLE   | R 0021, URBAN, TRAFFIC SIGNALS - 50% AURORA, 50% NAPERVILLE |
| E RETAINING WALL SN 022-W047 - 80% FED, 20% STATE                | L SHARED-USE PATH - 80% STATE, 20% NAPERVILLE                                  |   |
| F RETAINING WALL SN 022-W061 - 80% FED, 20% STATE                | M SHARED-USE PATH - 100% NAPERVILLE  |   |
| G TRAFFIC SIGNALS - 80% FED, 10% STATE, 5% NAPERVILLE, 5% AURORA | N ELECTRIC DUCT BANK - 100% NAPERVILLE   |   |

DESIGNED <i>PJO</i>	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
DRAWN <i>KES</i>	REVISED -		338	(112 & 113) WRS-7	DUPAGE	1156	9		
CHECKED <i>JCM</i>	REVISED -		CONTRACT NO. 60R30						
DATE <i>12/14/2012</i>	REVISED -		SCALE: NONE	SHEET NO. 4 OF 44 SHEETS	STA.	TO STA.			
ILLINOIS FED. AID PROJECT									