

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE																
				A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q
				0004 URBAN	0021 URBAN	0014 URBAN	0040 URBAN	0040 URBAN	0040 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0028 URBAN	0028 URBAN	0043 URBAN	0021 URBAN	0028 URBAN	0028 URBAN
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SO YD	858	858																
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SO YD	228	228																
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2																
50105220	PIPE CULVERT REMOVAL	FOOT	318	318																
50200100	STRUCTURE EXCAVATION	CU YD	1187					547	640											
50300225	CONCRETE STRUCTURES	CU YD	428.4	70.7				159.2	198.5											
50300285	FORM LINER TEXTURED SURFACE	SO FT	5421					2598	2823											
50500505	STUD SHEAR CONNECTORS	EACH	1098					496	602											
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	52710	7920				19780	25010											
50901750	PARAPET RAILING	FOOT	656	656																
51500100	NAME PLATES	EACH	1	1																

X SPECIALTY ITEM

- | | | |
|--|--|---|
| A ROADWAY AND DRAINAGE - 80% FED, 20% STATE | H TRAFFIC SIGNALS - 80% FED, 10% STATE, 10% NAPERVILLE | O ROADWAY - 100% STATE |
| B ROADWAY LIGHTING - 100% STATE | I TRAFFIC SIGNALS AND LIGHTING - 100% NAPERVILLE | P SHARED-USE PATH - 80% STATE, 20% AURORA |
| C B. N. S. F. RR BRIDGE SN 022-0038 - 80% FED, 20% STATE | J TRAFFIC SIGNAL INTERCONNECT / TEMPORARY TRAFFIC SIGNALS - 80% FED, 20% STATE | Q SHARED-USE PATH - 100% AURORA |
| D NOISE WALLS - 80% FED, 20% STATE | K SIDEWALK - 80% STATE, 20% NAPERVILLE | R 0021; URBAN, TRAFFIC SIGNALS - 50% AURORA, 50% NAPERVILLE |
| E RETAINING WALL SN 022-W047 - 80% FED, 20% STATE | L SHARED-USE PATH - 80% STATE, 20% NAPERVILLE | |
| F RETAINING WALL SN 022-W061 - 80% FED, 20% STATE | M SHARED-USE PATH - 100% NAPERVILLE | |
| G TRAFFIC SIGNALS - 80% FED, 10% STATE, 5% NAPERVILLE, 5% AURORA | N ELECTRIC DUCT BANK - 100% NAPERVILLE | |

DESIGNED <i>PJO</i>	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
DRAWN <i>KES</i>	REVISED -		SCALE: NONE	SHEET NO. 6 OF 44 SHEETS	STA.	33B	(112 & 113) WRS-7	DUPAGE	1156	11
CHECKED <i>JCM</i>	REVISED -					CONTRACT NO. 60R30				
DATE <i>12/14/2012</i>	REVISED -		ILLINOIS FED. AID PROJECT							