

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE																
				A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q
				0004 URBAN	0021 URBAN	0014 URBAN	0040 URBAN	0040 URBAN	0040 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0028 URBAN	0028 URBAN	0043 URBAN	0021 URBAN	0028 URBAN	0028 URBAN
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	32798	32798																
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	411	411																
60609100	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06 (VARIABLE WIDTH CUTTER FLAG)	FOOT	283	283																
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	323	323																
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	3420	3420																
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SO FT	1582	1582																
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SO FT	8373	8373																
60900515	CONCRETE THRUST BLOCKS	EACH	18	18																
X 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	150.0	150.0																
X 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1																
X 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1																

X SPECIALTY ITEM

- A ROADWAY AND DRAINAGE - 80% FED, 20% STATE
- B ROADWAY LIGHTING - 100% STATE
- C B.N.S.F. RR BRIDGE SN 022-0038 - 80% FED, 20% STATE
- D NOISE WALLS - 80% FED, 20% STATE
- E RETAINING WALL SN 022-W047 - 80% FED, 20% STATE
- F RETAINING WALL SN 022-W061 - 80% FED, 20% STATE
- G TRAFFIC SIGNALS - 80% FED, 10% STATE, 5% NAPERVILLE, 5% AURORA

- H TRAFFIC SIGNALS - 80% FED, 10% STATE, 10% NAPERVILLE
- I TRAFFIC SIGNALS AND LIGHTING - 100% NAPERVILLE
- J TRAFFIC SIGNAL INTERCONNECT / TEMPORARY TRAFFIC SIGNALS - 80% FED, 20% STATE
- K SIDEWALK - 80% STATE, 20% NAPERVILLE
- L SHARED-USE PATH - 80% STATE, 20% NAPERVILLE
- M SHARED-USE PATH - 100% NAPERVILLE
- N ELECTRIC DUCT BANK - 100% NAPERVILLE

- O ROADWAY - 100% STATE
- P SHARED-USE PATH - 80% STATE, 20% AURORA
- Q SHARED-USE PATH - 100% AURORA
- R 0021. URBAN, TRAFFIC SIGNALS - 50% AURORA, 50% NAPERVILLE

DESIGNED <i>PJO</i>	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
DRAWN <i>KES</i>	REVISED -		338	(112 & 113) WRS-7	DUPAGE	1156	21			
CHECKED <i>JCM</i>	REVISED -		SCALE: NONE		SHEET NO. 16 OF 44 SHEETS		STA.	TO STA.	CONTRACT NO. 60R30	
DATE <i>12/14/2012</i>	REVISED -		ILLINOIS FED. AID PROJECT							