	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE																
					A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q
					0004 URBAN	0021 URBAN	0014 URBAN	0040 URBAN	0040 URBAN	0040 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0028 URBAN	0028 URBAN	0043 URBAN	0021 URBAN	0028 URBAN	0028 URBAN
X	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	72							50	16	6								
X	88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1							1										
X	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	11							5	4	2								
X	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	39							26	8	5								
X	88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1									1								
X	88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	6							5		1								
X	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	18							8	4	6								
X	88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	10							10										
X	88102757	PEDESTRIAN SIGNAL HEAD, LED, 3-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	10							4	4	2								
X	88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	111							76	24	11								
X	88500100	INDUCTIVE LOOP DETECTOR	EACH	100							67	22	11								

X SPECIALTY ITEM

A ROADWAY AND DRAINAGE - 80% FED, 20% STATE
B ROADWAY LIGHTING - 100% STATE
C B.N.S.F. RR BRIDGE SN 022-0038 - 80% FED, 20% STATE
D NOISE WALLS - 80% FED, 20% STATE
E RETAINING WALL SN 022-W047 - 80% FED, 20% STATE
F RETAINING WALL SN 022-W061 - 80% FED, 20% STATE
G TRAFFIC SIGNALS - 80% FED, 10% STATE, 5% NAPERVILLE, 5% AURORA
H TRAFFIC SIGNALS - 80% FED, 10% STATE, 10% NAPERVILLE
I TRAFFIC SIGNALS AND LIGHTING - 100% NAPERVILLE
J TRAFFIC SIGNAL INTERCONNECT / TEMPORARY TRAFFIC SIGNALS - 80% FED, 20% STATE
K SIDEWALK - 80% STATE, 20% NAPERVILLE
L SHARED-USE PATH - 80% STATE, 20% NAPERVILLE
M SHARED-USE PATH - 100% NAPERVILLE
N ELECTRIC DUCT BANK - 100% NAPERVILLE
O ROADWAY - 100% STATE
P SHARED-USE PATH - 80% STATE, 20% AURORA
Q SHARED-USE PATH - 100% AURORA
R 0021, URBAN, TRAFFIC SIGNALS - 50% AURORA, 50% NAPERVILLE

	DESIGNED PJO	REVISED -	
	DRAWN KES	REVISED -	
	CHECKED JCM	REVISED -	
	DATE 12/14/2012	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE | SHEET NO. 28 OF 44 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(112 & 113) WRS-7	DUPAGE	1156	33
		CONTRACT NO. 60R30		
		ILLINOIS FED. AID PROJECT		