

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE																
				A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q
				0004 URBAN	0021 URBAN	0014 URBAN	0040 URBAN	0040 URBAN	0040 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0028 URBAN	0028 URBAN	0043 URBAN	0021 URBAN	0028 URBAN	0028 URBAN
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	17	17																
X X0323898	CLOSED CIRCUIT TELEVISION DOME CAMERA	EACH	1									1								
X X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	8099										8099							
X X0324243	CLOSED CIRCUIT TELEVISION VIDEO CODEC	EACH	1									1								
X X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	23928					11023	12905											
X X0324456	DRILLING AND SETTING SOLDIER PILES (IN ROCK)	CU FT	42						42											
X0325034	MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, OPEN LIDS, RESTRICTOR PLATE	EACH	1	1																
X X0326461	CLOSED CIRCUIT TELEVISION EQUIPMENT, FIBER OPTIC DISTRIBUTION	EACH	1									1								
X X0326465	MODIFICATION OF EXISTING VIDEO DISTRIBUTION SYSTEM	L SUM	1									1								
X X0327572	2-WAY 2-3" PVC DUCT BANK 1 HIGH BY 2 WIDE	FOOT	440															440		
X X0327436	2 - WAY 2 - 6" PVC DUCT BANK 1 HIGH BY 2 WIDE	FOOT	1020															1020		
X X0327438	4 - WAY 4 - 6" PVC DUCT BANK 2 HIGH BY 2 WIDE	FOOT	260															260		
X X0327573	4-WAY 2-3" & 2-6" PVC DUCT BANK 2 HIGH BY 2 WIDE	FOOT	320															320		
X X0327439	6 - WAY 6 - 6" PVC DUCT BANK 2 HIGH BY 3 WIDE	FOOT	1355															1355		

X SPECIALTY ITEM

- | | | |
|--|--|---|
| A ROADWAY AND DRAINAGE - 80% FED, 20% STATE | H TRAFFIC SIGNALS - 80% FED, 10% STATE, 10% NAPERVILLE | O ROADWAY - 100% STATE |
| B ROADWAY LIGHTING - 100% STATE | I TRAFFIC SIGNALS AND LIGHTING - 100% NAPERVILLE | P SHARED-USE PATH - 80% STATE, 20% AURORA |
| C B.N.S.F. RR BRIDGE SN 022-0038 - 80% FED, 20% STATE | J TRAFFIC SIGNAL INTERCONNECT / TEMPORARY TRAFFIC SIGNALS - 80% FED, 20% STATE | Q SHARED-USE PATH - 100% AURORA |
| D NOISE WALLS - 80% FED, 20% STATE | K SIDEWALK - 80% STATE, 20% NAPERVILLE | R 0021, URBAN, TRAFFIC SIGNALS - 50% AURORA, 50% NAPERVILLE |
| E RETAINING WALL SN 022-W047 - 80% FED, 20% STATE | L SHARED-USE PATH - 80% STATE, 20% NAPERVILLE | |
| F RETAINING WALL SN 022-W061 - 80% FED, 20% STATE | M SHARED-USE PATH - 100% NAPERVILLE | |
| G TRAFFIC SIGNALS - 80% FED, 10% STATE, 5% NAPERVILLE, 5% AURORA | N ELECTRIC DUCT BANK - 100% NAPERVILLE | |

Rev. 2-22-13

DESIGNED PJO	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
DRAWN KES	REVISED -		338	(112 & 113) WRS-7	DUPAGE	1156	40			
CHECKED JCM	REVISED -		SCALE: NONE		SHEET NO. 35 OF 44 SHEETS		STA. TO STA.		CONTRACT NO. 60R30	
DATE 12/14/2012	REVISED -		ILLINOIS FED. AID PROJECT							