



**SOUTH ELEVATION**  
(Looking North)

**NOTES**

1. The west span is 46'-2 1/2" long and consists of 18 built-up steel beams with a 36" web. The east span which is 42'-7 1/2" long consists of 18-W36 steel beams.
2. Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.

**BILL OF MATERIAL**

ITEM	UNIT	QUANTITY
Epoxy Crack Injection	Foot	3
Cleaning and Painting Exposed Rebar	Sq. Ft.	3
Cleaning Bridge Seats	Sq. Ft.	562

FILE NAME: ... \BPT38-0038-002-SupRepairs.dgn

DESIGNED - LAS	REVISED -
CHECKED - DAZ	REVISED -
DRAWN - SAW	REVISED -
CHECKED - LAS	REVISED -
SCALE - NONE	
DATE - 12/14/2012	

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(112 & 113) WRS-7	DUPAGE	1156	843
			CONTRACT NO. 60R30	
ILLINOIS FED. AID PROJECT				