FOR CONTINUATION OF IMPROVEMENT
SEE NEW YORK ST. / AURORA AVE.
PLAN-PROFILE SHEET

NEW YORK STREET

PROPOSED RETAINING WALL (TYP.)

STA. 3907+29.90 ILLINOIS ROUTE 59 =
STA. 100+00.00 NEW YORK ST./AURORA AVE.

PROPOSED RETAINING WALL (TYP.)

EXISTING R.O.W.

~ PROPOSED IL RTE 59

~ PROPOSED IL RTE 59

PROPOSED R.O.W.

EXISTING R.O.W.

RW-01 RW-02 RW-03

ILLINOIS ROUTE 59

RB-02

3900+00

3905+00

3910+00

MATCH LINE STA. 3900+00

MATCH LINE STA. 3914+00

100+00

RB-01

RB-03

EXISTING R.O.W.

PROPOSED R.O.W.

EXISTING R.O.W.

PROPOSED R.O.W.

AURORA AVENUE

N

50 0 50 100
HORIZONTAL SCALE: 1"=50'-0"

5 0 5 10
VERTICAL SCALE: 1"=5'-0"

PLAN	SURVEYED	BY	DATE
	PLOTTED		
	DRAWN BY		
	CHECKED		
	R.O.W. CHECKED		
NOTE BOOK	CADD FILE NAME		
NO.			

PROFILE	SURVEYED	BY	DATE
	PLOTTED		
	DRAWN		
	CHECKED		
NOTE BOOK	BAL NOTED		
NO.	STRUCTURE NO	TATHS CHKD	

① 1.0'-2.5' CLAY LOAM (A-7) LL=41 PL=22 PI=19 G.I.=13

② 6.0'-7.5' TOPSOIL O.C.=3.0%

~ NEW YORK ST./ AURORA AVE.
STA. 3907+29.90

RB-01
3901+75
63.0' Right
696.5

	N	Qu	W%
TOPSOIL	AS	-	23
	10	8.8S	19
	11	3.25B	19
CLAY (A-6)	16	4.0B	19
	17	5.4B	13

EOB

RB-02
3905+00
55.5' Left
694.1

	N	Qu	W%
TOPSOIL	AS	-	24
	9	3.5P	18
CLAY LOAM FILL (A-6)	11	3.3B	22
TOPSOIL	9	1.7B	31
SILTY CLAY (A-7)	5	0.75P	31
	9	3.3B	19
SILTY CLAY (A-6)	12	4.0B	19
	12	NP	20
SAND (A-3)	13	NP	18

EOB

RB-03
3908+75
62.5' Right
693.4

	N	Qu	W%
TOPSOIL	AS	-	24
	8	3.0P	21
CLAY LOAM (FILL)	8	-	28
SILTY CLAY LOAM (A-6)	11	2.7B	19
CLAY (A-6)	19	3.5B	18

EOB

RW-01
3911+37
75.0' Left
698.0

	N	Qu	W%
	AS	-	24
	7	4.25B	18
CLAY (FILL)	4	4.5P	22
	6	1.0P	22
CLAY LOAM (A-6)	6	2.25B	15
	50/1"	-	16
GRAVEL (A-1)	57	NP	1
	15	2.75B	17
CLAY (A-6)	14	2.9B	19

EOB

RW-03
3912+87
73.5' Left
700.2

	N	Qu	W%
	AS	-	31
TOPSOIL	8	-	28
	7	2.2B	24
	7	1.5B	22
	12	4.9B	16
CLAY (A-6)	22	3.2B	16
	13	3.5B	19
	17	4.3B	16
SAND (A-3)	17	NP	22

EOB

705 700 695 690 685 680 675 670

697.74 696.98 696.28 695.73 695.34 695.08 694.83 694.58 694.33 694.08 693.83 693.58 693.40 693.39 693.53 693.82 694.27 694.77 695.27 695.77 696.27 696.77 697.27 697.77 698.27 698.77

3902+00 3903+00 3904+00 3905+00 3906+00 3907+00 3908+00 3909+00 3910+00 3911+00 3912+00 3913+00 3914+00

Geo Services, Inc.
Geotechnical, Environmental & Civil Engineering
805 Amherst Court, Suite 204
Naperville, Illinois 60565
(630) 355-2838

USER NAME =	DESIGNED - RWC	REVISED -	
	DRAWN - RWC	REVISED -	
PLOT SCALE =	CHECKED - AJP	REVISED -	
PLOT DATE =	DATE - 3/24/2011	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SOIL BORING
PLAN / PROFILE ILLINOIS ROUTE 59

SCALE: | SHEET NO. OF SHEETS | STA. 3900+00 | TO STA. 3914+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338/IL 59	~~(12 & 13) WRS-5~~	DUPAGE	1156	878
		CONTRACT NO. 60R30		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		