FOR CONTINUATION OF IMPROVEMENT
SEE NEW YORK ST. / AURORA AVE.
PLAN-PROFILE SHEET

STA. 3976+49.56 ILLINOIS ROUTE 59 =
STA. 100+00.00 NORTH AURORA RD.

N

NORTH AURORA ROAD

PROPOSED RETAINING WALL

~ PROPOSED IL RTE 59

PROPOSED R.O.W.

EXISTING R.O.W.

MATCH LINE STA. 3969+00

NW-01

ILLINOIS ROUTE 59

NW-02

NW-03

3970+00

3975+00

RB-18

RB-19

RB-20

RB-21

3980+00

100+00

RB-04

EXISTING R.O.W.

PROPOSED R.O.W.

NORTH AURORA ROAD

PROPOSED R.O.W.

EXISTING R.O.W.

MATCH LINE STA. 3983+00

HORIZONTAL SCALE: 1"=50'-0"

VERTICAL SCALE: 1"=5'-0"

~ NORTH AURORA ROAD
STA. 3976+49.56

NW-01
3971+50
61.0' Left
700.1

	N	Qu	W%
TOPSOIL			
SILTY CLAY (A-6)	AS	-	37
	12	2.7B	24
	8	1.8B	26
	10	1.5P	23
CLAY (A-6)	16	6.2B	19
	18	5.5B	18
	14	4.5P	18
	18	5.9B	17
	15	3.9B	19

EOB

RB-18
3974+00
48.0' Right
703.9

	N	Qu	W%
TOPSOIL	AS	-	15
CLAY LOAM FILL (A-6)	9	1.75P	13
SILTY CLAY (A-6)	9	1.5P	29
	II	2.25P	14
CLAY (A-6)	20	6.7B	18
	26	4.5+P	19
	34	NP	6
SAND & GRAVEL (A-1)	56	NP	3
	32	NP	9

EOB

NW-03
3975+50
74.0' Left
703.8

	N	Qu	W%
SANDY TOPSOIL			
SILTY CLAY (A-6)	AS	-	26
	15	-	20
	48	-	13
CLAY LOAM (A-6)	52	4.5P	9
	35	4.5P	16
	16	5.0B	17
	18	4.4B	19
CLAY (A-6)	16	3.7B	19
	40	2.9B	15

EOB

RB-19
3978+00
49.0' Left
705.8

	N	Qu	W%
	AS	-	25
TOPSOIL	12	2.75P	22
CLAY LOAM FILL (A-6)	II	-	18
SAND & GRAVEL (A-1)	5	NP	9
CLAY (A-6)	9	3.5P	17

EOB

RB-20
3980+00
55.5' Right
706.2

	N	Qu	W%
TOPSOIL	AS	-	24
CRUSHED STONE	22	NP	5
	14	4.3S	14
	18	3.8S	16
	22	8.8B	16
CLAY (A-6)	23	4.6B	17
	14	4.0B	15
	15	2.25B	20
	II	2.25B	21

EOB

RB-21
3983+00
36.0' Left
707.7

	N	Qu	W%
TOPSOIL			
CLAY LOAM FILL (A-6)	27	NP	18
SILTY CLAY (A-6)	14	1.1B	26
SAND & GRAVEL (A-1)	II	NP	9
CLAY (A-6)	13	5.3B	15

EOB

710 / 705 / 700 / 695 / 690 / 685 / 680 / 675

693.33 694.53 695.72 696.92 698.12 699.32 700.51 701.69 702.72 703.57 704.26 704.78 705.12 705.32 705.49 705.67 705.84 706.02 706.19 706.37 706.55 706.72 706.90 707.07 707.25 707.42 707.60 707.77 707.95

3969+00 3970+00 3971+00 3972+00 3973+00 3974+00 3975+00 3976+00 3977+00 3978+00 3979+00 3980+00 3981+00 3982+00 3983+00

PLAN
SURVEYED
PLOTTED
ALIGNMENT CHECKED
RT. OF WAY CHECKED
C400 FILE NAME
NOTE BOOK
NO.
BY
DATE

PROFILE
SURVEYED
PLOTTED
CROSS SECS CHECKED
BM. NOTED
STRUCTURE NOTATNS CKD
NOTE BOOK
NO.
BY
DATE

Geo Services, Inc.
Geotechnical, Environmental & Civil Engineering
805 Amherst Court, Suite 204
Naperville, Illinois 60565
(630) 355-2838

USER NAME =		DESIGNED - RWC	REVISED -		
		DRAWN - RWC	REVISED -		
PLOT SCALE =		CHECKED - AJP	REVISED -		
PLOT DATE =		DATE - 3/24/2011	REVISED -		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SOIL BORING
PLAN / PROFILE ILLINOIS ROUTE 59

SCALE: | SHEET NO. OF SHEETS | STA. 3969+00 TO STA. 3983+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338/IL 59	~~(12 & 13) WRS-5~~	DUPAGE	1156	883
		CONTRACT NO. 60R30		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		