

SEQUENCE OF CONSTRUCTION:

- 1. CLOSE EXISTING VALVE.
- 2. REMOVE EXISTING HYDRANT.
- 3. INSTALL HYDRANT EXTENSION AND NEW VALVE.
- 4. RELOCATE EXISTING HYDRANT.
- 5. OPEN EXISTING VALVE, REMOVE BOX.
- 6. BACKFILL.
- 7. FLUSH AND TEST FOR CHLORIDE RESIDUAL AND PROVIDE TEST.

ALL WORK TO BE DONE IN ACCORDANCE WITH ARTICLE 564 OF THE STANDARD SPECIFICATIONS. NEW VALVE AND BOX SHALL BE SAME MAKE AND MODEL AS EXISTING.

## FIRE HYDRANT TO BE MOVED

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME =	USER NAME = gaglianobt	DESIGNED -	REVISED - R. SHAH 09-09-94		FIRE HYDRANT TO BE MOVED			RTF.	SECTION	COUNTY	SHEETS	NO.
W:\diststd\22x34\bd36.dgn		DRAWN -	REVISED - R. SHAH 10-25-94	STATE OF ILLINOIS		THE HIDIART TO BE MOVED		338	(112 & 113) WRS-7	DUPAGE	1156	895
	PLOT SCALE = 50.0000 '/ IN.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION					BD-36	CONTRACT	T NO.601	R30
	PLOT DATE = 1/4/2008	DATE -	REVISED -	SCALE	SCALE: NONE	SHEET NO. 1 OF 1 SHEETS STA.	TO STA.	FED. R	OAD DIST. NO. 1   ILLINOIS FED.			