CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE																				
				A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T
				0004	0021	0040	0040	0040	0040	0040	0040	0040	0040	0040	0021	0021	0021	0021		0028			0021
				URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	4217	4217																			
44000300	CURB REMOVAL	FOOT	622	622																			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	31704	31704																			
44000600	SIDEWALK REMOVAL	SQ FT	39387	39387																			
44003100	MEDIAN REMOVAL	SQ FT	8648	8648																			
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	152	152																			
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	3471	3471																			
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	418	418																			
50100300	REMOVAL OF EXISTING STRUCTURES NO.1	EACH	1	1																			
50200100	STRUCTURE EXCAVATION	CU YD	2447				284	164	230	295	501	130	616	227									
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2																			
50300225	CONCRETE STRUCTURES	CU YD	683.5				63.5	60.8	92.2	63.6	151.7	23.1	159.2	69.4									
50300285	FORM LINER TEXTURED SURFACE	SQ FT	2335				404		1184	747													
50500505	STUD SHEAR CONNECTORS	EACH	750				170	197	216	167													

X SPECIALTY ITEM

A ROADWAY AND DRAINAGE - 80% FED, 20% STATE
B ROADWAY LIGHTING - 100% STATE
C NOISE WALLS - 80% FED, 20% STATE
D RETAINING WALL SN 022-W048 - 80% FED, 20% STATE
E RETAINING WALL SN 022-W049 - 80% FED, 20% STATE
F RETAINING WALL SN 022-W051 - 80% FED, 20% STATE
G RETAINING WALL SN 022-W053 - 80% FED, 20% STATE
H RETAINING WALL SN 022-W054 - 80% FED, 20% STATE
I RETAINING WALL SN 022-W058 - 80% FED, 20% STATE
J RETAINING WALL SN 022-W059 - 80% FED, 20% STATE
K RETAINING WALL SN 022-W060 - 80% FED, 20% STATE
L TRAFFIC SIGNALS - 80% FED, 10% STATE, 5% NAPERVILLE TWP, 5% NAPERVILLE
M TRAFFIC SIGNALS - 80% FED, 10% STATE, 10% NAPERVILLE
N TRAFFIC SIGNALS AND LIGHTING - 100% NAPERVILLE
O TRAFFIC SIGNAL INTERCONNECT - 80% FED, 20% STATE
P SIDEWALK - 80% STATE, 20% NAPERVILLE
Q SHARED-USE PATH - 80% STATE, 20% NAPERVILLE
R SHARED-USE PATH - 100% NAPERVILLE
S ROADWAY - 100% STATE
T SIDEWALK - 100% NAPERVILLE TWP

DESIGNED PJO	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES
DRAWN KES	REVISED -		
CHECKED JCM	REVISED -		
DATE 12-17-2012	REVISED -		SCALE: NONE SHEET NO. 5 OF 36 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(112 & 113) WRS-6	DUPAGE	734	9
		CONTRACT NO. 60R31		
		ILLINOIS FED. AID PROJECT		