COMMITMENTS

No Commitments have been made for this project.

GENERAL NOTES

Location 1,2 & 4 The entire Structure shall be done in accordance with Section 592 of the "Standard Specifications Road and Bridge Construction" Adopted January 1, 2012.

No additional compensation shall be allowed for work in section 592.04

Location 3 shall be washed in accordance with Section 592 of the "Standard Specifications for Road and Bridge Construction" Adopted January 1, 2012. The areas to be washed as designated in the plans. These areas shall include drain troughts beneath the expansion devices and 10' either side of the expansion joints, top of pier caps and abutments immediately adjacent of the expansion joint. Entire Bridge deck, curb, sidewalk, drains and drainage systems.

No additional compensation shall be allowed for work in section 592.04

FILE NAME :	USER NAME & oubrouge	DESIGNED -	REVISED -		T	w ,v,		***************************************		F.A.	SECTION	COUNTY	TOTAL SHEET
68821-Bridge Washing 2013.dgn		ORAWN -	REVISED -	STATE OF ILLINOIS	1					VAR D4	BRIDGE WASHING 2013	VARIOUS	B 4
	PLOT SCALE + 180,8888 */ in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	1							CONTRAC	T NO. 68B21
Default	PLOT DATE + 3/26/2013	DATE -	REVISED -		SCALE:	SCALE: SHEET OF SHEETS STA. TO STA.				<u> </u>	ILLINOIS FED. AID PROJECT		