

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	10-00009-00-BR	FRANKLIN	11	2
VILLAGE OF ROYALTON		MAIN STREET		

CONTRACT NO. 99502

SUMMARY OF QUANTITIES

* - SPECIAL PROVISION

CODE NO.	PAY ITEM	UNIT	QUANTITY
X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.5
Δ * XX004731	CONNECTION TO EXISTING WATERMAIN	EACH	2
Δ * XX005890	DETECTION WIRE	FOOT	340
Δ * XX006538	WATER MAIN 6, BORED	FOOT	300
Δ * XX003796	TAP + CORR., 1"	EACH	1
20200100	EARTH EXCAVATION	CU YD	200
20400100	BORROW EXCAVATION	CU YD	300
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	150
*28000305	TEMPORARY DITCH CHECKS	FOOT	80
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	250
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	475
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50105220	PIPE CULVERT REMOVAL	FOOT	70
50300225	CONCRETE STRUCTURES	CU YD	22.6
50300280	CONCRETE ENCASMENT	CU YD	3.5
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ FT	1560
50800105	REINFORCEMENT BARS	POUND	2680
Δ 50900205	STEEL RAILING, TYPE S1	FOOT	130
51201400	FURNISHING STEEL PILES HP10X42	FOOT	550
51202305	DRIVING PILES	FOOT	550
51500100	NAME PLATES	EACH	1
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	65
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	100
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 24"	EACH	2
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 36"	EACH	1
Δ * 56100600	WATER MAIN 6	FOOT	40
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1
67100100	MOBILIZATION	L SUM	1

Δ SPECIALTY ITEMS

