

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE			
				PCC PAVEMENT J000-2A	LIGHTING Y030-1E	I.T.S. Y032-1F	SIGNING Y002-1C
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	6358	6358			
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	905	905			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	702	702			
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	1024	1024			
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8			
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	66	66			
* 78201000	TERMINAL MARKERS, DIRECT APPLIED	EACH	2	2			
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	3693	3693			
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	153		153		
* 81023750	CONDUIT ENCASED IN CONCRETE, 3" DIA., PVC	FOOT	138			138	
* 81400200	HEAVY DUTY HANDHOLE	EACH	4		4		
* 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	399		399		
* 84200705	LIGHTING FOUNDATION REMOVAL, PARTIAL	EACH	26		26		
* X2500322	SEEDING, CLASS 5A (MODIFIED)	ACRE	0.50	0.50			
* C2C05818	SHRUB, RHUS AROMATICA GRO-LOW (GROW-LOW FRAGRANT SUMAC), 18" WIDTH, CONTAINER	EACH	225	225			
* E20200G1	VINE-PARTHENOCISSUS QUINQUEFOLIA (VIRGINIA CREEPER), 1-GALLON POT	EACH	95	95			
* K0030400	PERENNIAL PLANTS, DAYLILIES	UNIT	1	1			
⊙ X0320333	ROADWAY CLEANING (SPECIAL)	EACH	28	28			
* X0321866	REMOVE, STORE AND RE-ERECT SIGN PANEL	SQ FT	84				84
* X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	421	32			389
X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	1050	1050			
* X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	2	2			
* X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	26	26			
* X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	2516	2516			
* X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	629	629			
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	2560	2560			
X0324112	BARRIER BASE	FOOT	6351	6351			
* X0324646	CONDUIT ENCASED, REINFORCED CONCRETE, 6 - 4" DIA., CNC	FOOT	246		246		
X0324697	SOIL STABILIZERS	POUND	62000	62000			
X0324698	APPLYING DUST SUPPRESSION AGENTS	UNIT	34	34			
X0325082	CTA BARRIER REMOVAL	FOOT	4981	4981			
* X0325083	CTA FENCE	FOOT	5003	5003			

- * - SPECIALTY ITEM
- - IDOT PAY CODE SFTY-3N
- △ - IDOT PAY CODE Y080.
- ⊙ - NON-PARTICIPATING

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
 SHEET 4 OF 5

SCALE: NONE
 DATE: MARCH 1, 2006

DRAWN BY: MPG
 CHECKED BY: TCB