

PROPOSED GROUND-MOUNTED SIGN SCHEDULE

LOCATION	STATION	SIGN				SUPPORT			SIGN REMARKS
		TYPE	WIDTH, FT	HEIGHT, FT	AREA, SQ FT	TYPE	POST QUANTITY	POST LENGTH (FT)	
SB I-94 (DAN RYAN)	1318+19	3	7.5	5	37.5	WOOD	2	34	EXIT 60C & ARROW
SB I-94 (DAN RYAN)	1323+40	2	4	4	16	WOOD	1	17.66	W4-1R
SB I-94 (DAN RYAN)	1328+38	1	1	4	4	TELES. STEEL	1	13.83	D10-2A (60.5)
SB I-94 (DAN RYAN)	1329+12	2	4	4	16	WOOD	1	17.66	W4-3R
SB I-94 (DAN RYAN)	1331+82	3	7.5	5	37.5	WOOD	2	34	EXIT 60C & ARROW
SB I-94 (DAN RYAN)	1342+50	1	2.5	1.25	3.125	WOOD	1	16.25	M3-2(INTERSTATE)
		1	3	3	9				M1-1 (94)
SB I-94 (DAN RYAN)	1354+78	1	1	4	4	TUBULAR POST	1	8	D10-2A (60.0)
SB I-94 (DAN RYAN)	1355+91					SIGN PANEL RELOCATED TO EXISTING TRUSS SUPPORT			*999 CELLULAR EXPRESS LINE

REVISIONS	
NAME	DATE