


## INDEX OF SHEETS

1. COVER SHEET
2. INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES, & COMMITMENTS
3. SUMMARY OF QUANTITIES
- 4-5. TYPICAL SECTIONS
6. SCHEDULES OF QUANTITIES
7. LOCATION MAP

## HIGHWAY STANDARDS

- 000001-08 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS  
 001006 DECIMAL OF AN INCH AND OF A FOOT  
 701006-05 OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE  
 701011-04 OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY  
 701306-04 LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS  $\geq$  45 MPH  
 701311-03 LANE CLOSURE 2L, 2W MOVING OPERATIONS - DAY ONLY  
 701901-08 TRAFFIC CONTROL DEVICES  
 780001-05 TYPICAL PAVEMENT MARKINGS  
 781001-04 TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS

 701201-05 LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS  $\geq$  45 MPH

## GENERAL NOTES

1. THE UTILITIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:

UTILITY	TYPE	JULIE MEMBER
- FRONTIER COMMUNICATIONS 117 W. JEFFERSON STREET MT. PULASKIAL, IL 62548	COMMUNICATIONS	YES
- GREENE COUNTY RURAL WATER DISTRICT 323A 6TH STREET CARROLLTON, IL 62016	WATER	YES
- ILLINOIS ELECTRIC COOPERATIVE TWO S. MAIN STREET WINCHESTER, IL 62694-0010	ELECTRIC	YES


2. NO SURVEY WAS PERFORMED FOR THIS PROJECT AND THE PLANS WERE CREATED USING MICROFILM AND FIELD MEASUREMENTS.
3. THE MTD MAY OPERATE IN AN UNLOADED CONDITION ON SN 031-0028, SN 031-2415, AND SN 031-2416.
4. THE TEMPORARY RAMPS USED ON ALL SIDE STREETS AND ENTRANCES SHALL BE 1.50 FEET IN LENGTH SO AS NOT TO INTERFERE WITH THE THRU TRAFFIC LANES.
5. THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT:

MIXTURE USE	SURFACE
AC/PG	PG 64-22
RAP %(MAX)	SEE SPECIAL PROVISION
DESIGN AIR VOIDS	4.0% @ Ndes=70
MIX COMPOSITION (GRADATION)	IL 9.5
FRICTION AGG	MIXTURE "C"
QUALITY MGMT PROGRAM	QCP

PLAN QUANTITIES FOR HOT-MIX ASPHALT ITEMS ARE CALCULATED USING A UNIT WEIGHT OF 112 LBS/SQ YD/IN

## COMMITMENTS

NONE

 REVISED 5-28-2021

MODEL: Default  
 FILE: M:\MTC\_PlanRoom\room.dat\illinois.gov\WIDOT\Documents\DOT\_Offices\District 8\Projects\0876P25\CADDData\CAD\sheet\0876P25-ht-genote.dgn

USER NAME = humphreysb	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 3/8/2021	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS, HIGHWAY STANDARDS,  
GENERAL NOTES, AND COMMITMENTS

SCALE: NTS SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
761	(104,107)R5-3	GREENE	7	2
				CONTRACT NO. 76P25
ILLINOIS FED. AID PROJECT				

MODEL: Default  
 FILE NAME: P:\p1g1amcom.dct\illinois.gov\PIWDOT\Documents\DOT\_Offices\District\_B\Project\0876P25\Cadd\Cadd\Cadd\Sheet\0876P25-ht500.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				80% FEDERAL
				20% STATE
				ROADWAY
				0005
				RURAL
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	22008	22008
40600990	TEMPORARY RAMP	SQ YD	92	92
40604052	HOT-MIX ASPHALT SURFACE COURSE, 1L-9.5, MIX "C", N70	TON	4110	4110
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	48904	48904
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	172	172
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	648	648
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4680	4680
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	524	524
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	44741	44741
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	44741	44741
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	218	218

\* SPECIALTY ITEM

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				80% FEDERAL
				20% STATE
				ROADWAY
				0005
				RURAL
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	218	218
X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT	14917	14917
Z0033700	LONGITUDINAL JOINT SEALANT	FOOT	16955	16955
Ø Z0076600	TRAINEES	hour	500	500
Z0034105	MATERIAL TRANSFER DEVICE	TON	4110	4110
Ø Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	hour	500	500

Ø 0042



△ REVISED 5-28-2021

REV. - MS

USER NAME = humphreysb	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 3/8/2021	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: NTS    SHEET 1 OF 1 SHEETS    STA.    TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
761	(104,107)RS-3	GREENE	7	3
ILLINOIS FED. AID PROJECT			CONTRACT NO. 76P25	