

CODE NO.	ITEM	UNIT	TOTAL QUANTITY URBAN	CONSTRUCTION CODE	
				80% FED, 20% STATE	80% FED, 20% STATE
				BRIDGE	RETAINING WALL
				0004 SN: 022-8300	0044 SN: 022-W001
50201101	COFFERDAM (TYPE 1) (LOCATION - 1)	EACH	2	2	
50300285	FORM LINER TEXTURED SURFACE	SQ FT	4,232		4,232
50300300	PROTECTIVE COAT	SQ YD	515		515
50500505	STUD SHEAR CONNECTORS	EACH	1,234		1,234
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	34,670	2,320	32,350
50901760	PIPE HANDRAIL	FOOT	403		403
* 51204650	PILE SHOES	EACH	56		56
* 51500100	NAME PLATES	EACH	2	1	1
* 52200015	PERMANENT SHEET PILING	SQ FT	736	736	
* 52200020	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1,764	1,764	
* 52200105	FURNISHING SOLDIER PILES (W SECTION)	FOOT	1,710		1,710
* 52200150	DRIVING SOLDIER PILES	FOOT	1,710		1,710
* 52200250	UNTREATED TIMBER LAGGING	SQ FT	4,498		4,498
52200900	CONCRETE STRUCTURES (RETAINING WALL)	CU YD	174.1		174.1
54003000	CONCRETE BOX CULVERTS	CU YD	31.9	31.9	

* SPECIALTY ITEM

MODEL: D:\p1\11111111 - IDOT\040589-01-002 (ENG) - PTB 195-016 Phase II Vpr Vpr\Engineering\WO 1 - IL\241381500 Drawings\502 CADD Sheets\ID162M69-sh-50003.dgn
 FILE NAME: P10100589 - IDOT\040589-01-002 (ENG) - PTB 195-016 Phase II Vpr Vpr\Engineering\WO 1 - IL\241381500 Drawings\502 CADD Sheets\ID162M69-sh-50003.dgn



USER NAME = khejtmanek	DESIGNED - KH	REVISED -
DRAWN - KM	CHECKED - AP	REVISED -
PLOT SCALE = 2.0000' / in.	DATE - 3/11/2021	REVISED -
PLOT DATE = 3/10/2021		

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: NONE	SHEET 3	OF 6 SHEETS	STA. TO STA.

F.A.P. RTE. 344	SECTION 2020-196-T	COUNTY	TOTAL SHEETS 122	SHEET NO. 6
CONTRACT NO. 62M69			ILLINOIS FED. AID PROJECT	

REV-SEP