

CODE NO.	ITEM	UNIT	TOTAL QUANTITY URBAN	CONSTRUCTION CODE	
				80% FED, 20% STATE	80% FED, 20% STATE
				BRIDGE 0004 SN: 022-8300	RETAINING WALL 0044 SN: 022-W001
* 66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	LSUM			
* 66901006	REGULATED SUBSTANCES MONITORING	CAL DA			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12	
67100100	MOBILIZATION	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	133	133	
70107005	PAVEMENT MARKING BLACKOUT TAPE, 5"	FOOT	4,760	4,760	
70107009	PAVEMENT MARKING BLACKOUT TAPE, 9"	FOOT	185	185	
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1	
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	1,696	1,696	
70300904	PAVEMENT MARKING TAPE, TYPE IV 4"	FOOT	22,558	22,558	
70300908	PAVEMENT MARKING TAPE, TYPE IV 8"	FOOT	11,486	11,486	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	3,475	3,475	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	3,788	3,788	
70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4	4	
70600270	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, WIDE), TEST LEVEL 3	EACH	1	1	

\* SPECIALTY ITEM

MODEL: D:\c\it...  
 FILE NAME: P:\0\0058...  
 ID: 010005801-002 (ENG) - PTB 195-016 Phase II Vpr Vpr\Engineering\WO 1 - IL024L3B500 Drawings\502 CADD Sheets\62M69-sht-50005.dgn



USER NAME = khejtmanek	DESIGNED - KH	REVISED -
DRAWN - KM	CHECKED - AP	REVISED -
PLOT SCALE = 2.0000' / in.	DATE - 3/11/2021	REVISED -
PLOT DATE = 3/10/2021		

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: NONE    SHEET 5 OF 6 SHEETS    STA.    TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
344	2020-196-T	DUPAGE	122	8
CONTRACT NO. 62M69			ILLINOIS FED. AID PROJECT	

REV-SEP