	CODE NO.	ITEM	UNIT	TOTAL QUANTITY URBAN	CONSTRUCTION CODE 80% FED, 20% STATE BRIDGE 0004 SN: 022-8300	80% FED, 20% STATE RETAINING WALL 0044 SN: 022-W001	
	70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	8	8		
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8,000	8,000		
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,832	1,832		
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	872	872		
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	242	242		
*	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	175	175		
*	81603080	UNIT DUCT, 600V, 3-1C NO.2, 1/C NO.4 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	1,690	1,690		
*	81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	1,463	1,463		
*	82110008	LUMINAIRE, LED, ROADWAY, OUTPUT DESIGNATION H	EACH	14	14		
*	83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	8	8		
*	83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	6	6		
*	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	80	80		
*	83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	8	8		
*	84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	6	6		
*	84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	7	7		
*	84200804	REMOVAL OF POLE FOUNDATION	EACH	7	7		

* SPECIALTY ITEM

REV-SEP